

80% FED.
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0011
CODE NO	ITEM	UNIT		
20200100	EARTH EXCAVATION	CU YD	82	82
20400800	FURNISHED EXCAVATION	CU YD	1039	1039
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	36	36
28000305	TEMPORARY DITCH CHECKS	FOOT	14	14
28000400	PERIMETER EROSION BARRIER	FOOT	405	405
28100107	STONE RIPRAP, CLASS A4	SQ YD	730	730
28200200	FILTER FABRIC	SQ YD	730	730
35101400	AGGREGATE BASE COURSE, TYPE B	TON	26	26
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	152	152
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	290	290
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	282	282
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	76	76
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	13	13
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	37	37
44000100	PAVEMENT REMOVAL	SQ YD	207	207
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	616	616
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	763	763
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
50200100	STRUCTURE EXCAVATION	CU YD	134	134
50300100	FLOOR DRAINS	EACH	14	14
50300225	CONCRETE STRUCTURES	CU YD	69.6	69.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	242	242
50300260	BRIDGE DECK GROOVING	SQ YD	535	535
50300280	CONCRETE ENCASEMENT	CU YD	8.6	8.6
50300300	PROTECTIVE COAT	SQ YD	713	713
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1
50500505	STUD SHEAR CONNECTORS	EACH	2034	2034
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	64100	64100
50800515	BAR SPLICERS	EACH	68	68
51201400	FURNISHING STEEL PILES HP10X42	FOOT	820	820
51201800	FURNISHING STEEL PILES HP14X73	FOOT	430	430
51202305	DRIVING PILES	FOOT	1250	1250
51203400	TEST PILE STEEL HP10X42	EACH	2	2

80% FED.
20% STATE

SUMMARY OF QUANTITIES (Cont'd)			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0011
CODE NO	ITEM	UNIT		
51203800	TEST PILE STEEL HP14X73	EACH	1	1
51204650	PILE SHOES	EACH	18	18
51500100	NAME PLATES	EACH	1	1
52100520	ANCHOR BOLTS, 1"	EACH	36	36
54213453	END SECTIONS 18"	EACH	2	2
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	24	24
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	50	50
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4	4
60100905	PIPE DRAINS 4"	FOOT	80	80
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	131	131
60900515	CONCRETE THRUST BLOCKS	EACH	8	8
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	312.5	312.5
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3
63200310	GUARDRAIL REMOVAL	FOOT	152	152
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	12.5	12.5
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	9	9
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	5
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	65	65
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	22	22
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1463	1463
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	9	9
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	2	2
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	81	81
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.4	0.4
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	2	2
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	1

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	S.B.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\pw\work\p\dot\swartzw\d0127784\077	004-ahs:soq.dgn	DRAWN -	REVISED -			12	10B-1	CLAY	39	3	
PLOT SCALE = 48,0000' / IN.		CHECKED -	REVISED -			SCALE: NA SHEET NO. 1 OF 1 SHEETS STA. TO STA.					
PLOT DATE = 8/12/2010		DATE -	REVISED -			CONTRACT NO. 74004					

*Specialty Items Rev.

ILLINOIS FED. AID PROJECT