

SUMMARY OF QUANTITIES

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | |
|-----------------------|---|--------|------------------|------------------------|--|--|-----------------------|---|-------|------------------|------------------------|--|--|
| CODE NO | ITEM | UNIT | | 100% STATE 0014 | | | CODE NO | ITEM | UNIT | | 100% STATE 0014 | | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 0.3 | 0.3 | | | 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 1282 | 1282 | | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 2 | 2 | | | 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 18 | 18 | | |
| 40600990 | TEMPORARY RAMP | SQ YD | 37 | 37 | | | X4420118 | CLASS A PATCHES (SPECIAL) | SQ YD | 80 | 80 | | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 17 | 17 | | | X5080600 | MECHANICAL SPLICERS | EACH | 40 | 40 | | |
| 44000155 | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" | SQ YD | 849 | 849 | | | X5210140 | HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 350K | EACH | 4 | 4 | | |
| 44201299 | DOWEL BARS 1 1/2" | EACH | 20 | 20 | | | X7010202 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL) | EACH | 1 | 1 | | |
| 44213000 | PATCHING REINFORCEMENT | SQ YD | 80 | 80 | | | Z0001899 | JACK AND REMOVE EXISTING BEARINGS | EACH | 4 | 4 | | |
| 44213200 | SAW CUTS | FOOT | 192 | 192 | | | Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | 2 | | |
| 44213204 | TIE BARS 3/4" | EACH | 14 | 14 | | | Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | 2 | | |
| 48203100 | HOT-MIX ASPHALT SHOULDERS | TON | 58 | 58 | | | Z0073350 | TEMPORARY SLAB SUPPORT SYSTEM | EACH | 1 | 1 | | |
| 50102400 | CONCRETE REMOVAL | CU YD | 19 | 19 | | | | | | | | | |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 17.4 | 17.4 | | | | | | | | | |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL | POUND | 2930 | 2930 | | | | | | | | | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 1720 | 1720 | | | | | | | | | |
| 50800515 | BAR SPLICERS | EACH | 26 | 26 | | | | | | | | | |
| 52000110 | PREFORMED JOINT STRIP SEAL | FOOT | 44.5 | 44.5 | | | | | | | | | |
| 52000216 | FINGER PLATE EXPANSION JOINT, 5" | FOOT | 39 | 39 | | | | | | | | | |
| 52000600 | FABRIC REINFORCED ELASTOMERIC TROUGH | FOOT | 41 | 41 | | | | | | | | | |
| 52100520 | ANCHOR BOLTS, 1" | EACH | 16 | 16 | | | | | | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 8 | 8 | | | | | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | | | | | |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 | | | | | | | | | |
| 70106500 | TEMPORARY BRIDGE TRAFFIC SIGNALS | EACH | 1 | 1 | | | | | | | | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 3857 | 3857 | | | | | | | | | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 1700 | 1700 | | | | | | | | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 1288 | 1288 | | | | | | | | | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 850 | 850 | | | | | | | | | |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 850 | 850 | | | | | | | | | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 235 | 235 | | | | | | | | | |
| * 78008210 | POLYUREA PAVEMENT MARKING TYPE I - LINE 4" | FOOT | 3622 | 3622 | | | | | | | | | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 11 | 11 | | | | | | | | | |
| * 78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 8 | 8 | | | | | | | | | |

*SPECIALTY ITEM

| | | | | | | | | | | |
|-------------|----------------------|----------------|-----------|---|------------------------------|-------------|-------------|--------------------|--------------|---------------------------|
| FILE NAME = | USER NAME = #USER# | DESIGNED - ACM | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| #FILE# | | DRAWN - ACM | REVISED - | | | 103 | 561-B-I | ST. CLAIR | 21 | 3 |
| | PLOT SCALE = #SCALE# | CHECKED - | REVISED - | | | | | CONTRACT NO. 76E20 | | |
| | PLOT DATE = #DATE# | DATE - | REVISED - | | SCALE: NONE | SHEET NO. 1 | OF 1 SHEETS | STA. | TO STA. | ILLINOIS FED. AID PROJECT |