## **STANDARDS**

000001-06 280001-05 420001-07 420111-03 420401-08 420501-04 424001-05 515001-03 542301-03 542601-03 602301-03 602401-03 602406-04 602601-02 602701-02 604001-03 604051-03 606001-04 667101-01 701001-02 701006-03 701011-02 701301-04 701311-03 701501-06 701901-01 720001-01 720006-02 780001-02 805001-01 B.L.R. 14-10 B.L.R. 21-8 630001-09 631031 - 09 BLR 23-3

THE FOLLOWING RATES OF APPLICATION HAVE BEEN ASSUMED IN CALCULATING PLAN QUANTITIES

AGGREGATE (SURFACE, BASE, SUBBASE, OR BACKFILL) 2.05 TON PER CUBIC YARD STONE DUMPED RIPRAP BITUMINOUS MATERIALS (PRIME COAT BITUMINOUS MATERIALS (PRIME COAT BITUMINOUS MATERIALS (COVER & SEAL COAT) COVER COAT AGGREGATE SEAL COAT AGGREGATE AGGREGATE (PRIME COAT) BITUMINOUS SURFACE/BINDER NITROGEN FERTILIZER NUTRIENT PHOSPHOROUS FERTILIZER NUTRIENT POTASSIUM FERTILIZER NUTRIENT AGRICULTURAL GROUND LIMESTONE MULCH LIME FOR MODIFIED SOILS, 12-INCH WATER FOR LIME MODIFIED SOILS, 12-INCH ROCKFILL-SUBGRADE

1.50 TON PER CUBIC YARD 0.00038 TON PER SQUARE YARD (ON PAVEMENT) 0.001425 TON PER SQUARE YARD (ON AGGREGATE) 0.001425 TON PER SQUARE YARD 0.01 TON PER SQUARE YARD 0.01 TON PER SQUARE YARD 0.002 TON PER SQUARE YARD 2.016 TON PER CUBIC YARD 90 LBS. PER ACRE 90 LBS. PER ACRE 90 LBS. PER ACRE 2 TON PER ACRE 2 TON PER ACRE 0.02 TON PER SQUARE YARD 0.007 UNITS PER SQUARE YARD (1 UNIT = 1000 GAL. 1.89 TONS PER CUBIC YARD

## **GENERAL NOTES**

- 1. ELEVATIONS ARE BASED ON N.G.S. VERTICAL DATUM OF 1929.
- THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER, AUTHORIZED AGENT, OR LAND SURVEYOR HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. WHERE SECTION OR SUB-SECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR RE-ESTABLISH ANY SECTION OR SUB-SECTION MONUMENTS DESTROYED BY HIS OPERATIONS.
- 3. ALL DISTURBED UNSURFACED AREAS WITHIN THE RIGHT OF WAY AND EASEMENTS SHALL BE SEEDED, FERTILIZED, AND MULCHED AS SHOWN IN THE PLANS, SPECIAL PROVISIONS AND AS DIRECTED BY THE ENGINEER. SEEDING WILL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET OR IN AN UNTILLABLE CONDITION.
- IN ACCORDANCE WITH STATE OF ILLINOIS P.A. 86-0674, THE CONTRACTOR IS TO NOTIFY ALL UTILITY COMPANIES NOT MORE THAN 14 DAYS NOR LESS THAN 48 HOURS (EXCLUSIVE OF SATURDAYS, SUNDAYS, AND HOLIDAYS) IN ADVANCE OF THE START OF EXCAVATION OR DEMOLITION.

J.U.L.I.E. TELEPHONE NUMBER 1-800-892-0123

KNOWN UTILITIES LOCATED WITHIN THE LIMITS OF THIS IMPROVEMENT ARE:

AMEREN CIPS (ELECTRIC)

700 JERSEY STREET QUINCY, IL 62306 PH. (217) 741-2503

AMEREN CIPS (GAS) 700 JERSEY ST QUINCY, IL 62301 PH. (217) 221-0800

CITY OF QUINCY PUBLIC UTILITIES (WATER, STORM, SANITARY SEWER) 2020 JENNIFER ROAD OUINCY II 62306 PH. (217) 228-4588

AMERITECH (TELEPHONE) 6TH & BROADWAY ST. QUINCY, IL 62301 PH. (217) 224-9661

- THE LOCATION OF BURIED AND ABOVE GROUND UTILITIES SHOWN ARE APPROXIMATE AND ARE SHOWN FOR CONTRACTOR INFORMATIONAL USE ONLY, AND ARE NOT TO BE REFERENCED FOR CONSTRUCTION PURPOSES. THE IMPLIED PRESENCE OR ABSENCE OR UTILITIES IS NOT TO BE CONSTRUED BY THE OWNER, ENGINEER, CONTRACTOR, OR SUBCONTRACTORS TO BE AN ACCURATE AND COMPLETE REPRESENTATION OF UTILITIES THAT MAY OR MAY NOT EXIST ON THE CONSTRUCTION SITE. BURIED AND ABOVE GROUND UTILITY LOCATIONS, IDENTIFICATION, AND MARKING ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. REFOUTING, DISCONNECTION, PROTECTION, ETC. OF ANY UTILITIES MUST BE COORDINATED BETWEEN THE CONTRACTOR, UTILITY COMPANY, AND OWNER. SITE SAFETY, INCLUDING THE AVOIDANCE OF HAZARDS ASSOCIATED WITH THE BURIED AND ABOVE GROUND UTILITIES REMAINS THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
- ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUB-NUMBER IN THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.
- 7. MAINTAIN EXISTING TRAFFIC CONTROL AT ALL INTERSECTIONS DURING CONSTRUCTION.
- 8. FERTILIZER NUTRIENTS SHALL BE APPLIED TO ALL SEEDING AREAS.
- BEFORE ORDERING PIPE CULVERTS OR PIPE DRAINS, THE CONTRACTOR SHALL CONSULT THE ENGINEER FOR EXACT LENGTHS.
- 10. ALL TREES, BRUSH AND SHRUBS WITHIN THE CONSTRUCTION LIMITS WILL BE REMOVED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS. TREES ALONG THE RIGHT OF WAY, OUTSIDE THE CONSTRUCTION LIMITS SHALL BE SAVED IF, IN THE OPINION OF THE ENGINEER, THEY DO NOT INTERFERE WITH CONSTRUCTION OPERATIONS. THE CONTRACTOR WILL PROTECT ALL REMAINING TREES FROM DAMAGE DUE TO HIS OPERATIONS.
- 11. UNLESS OTHERWISE NOTED, THE OFFSETS SHOWN IN THE PLANS FOR THE END OF PIPE CULVERTS ARE TO THE END OF THE LAST SECTION OF PIPE, NOT TO THE END OF THE END

		RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	Ν	5TH ST	03-00289-00-BR	ADAMS	90	2
STA. TO STA						
CONTRACT NO. 93542						

## **COMMITMENTS:**

QUINCY PARK DISTRICT RESERVES RIGHT TO FENCE DRIP-LINE OF TREES ALONG PERIMETER OF PROPOSED IMPROVEMENTS. NO PRUNING/CUTTING OF PERIMETER TREES IS ALLOW WITHOUT PARK DISTRICT APPROVAL.

1	PSBA POEPPING, STONE, BACH & ASSOCIATES, INC.				
	ARCHITECTS ENGINEERS PLANNERS SURVEYORS 100 S 54TH ST, P.O. BOX 709 • QUINCY, II. 62306 WITH OFFICES IN IKEOKUK, IOWA & HANNIBAL, MISSOURI www.psba.com.pHONE 877-223-4605				

CITY OF QUINCY, ILLINOIS

N. 5TH STREET BRIDGE GENERAL NOTES

AND STANDARDS

SCALE: VERT. HORIZ. DATE

NAME

DRAWN BY DBS CHECKED BY: AMW