



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 18, 2022

SUBJECT: FAP Route 599 (Andalusia Rd.)  
Project STP-UR8U(803)  
Section (48MFT, 62MFT)TS-1  
Rock Island County  
Contract No. 64M24  
Item No. 28, March 11, 2022 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised the Table of Contents to the Special Provisions.
3. Revised page 51 of the Special Provisions.
4. Added pages 52-53 to the Special Provisions.
5. Revised sheets 2, 10, and 12 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

## TABLE OF CONTENTS

|   |    |
|---|----|
| LOCATION OF PROJECT .....                                   | 1  |
| DESCRIPTION OF PROJECT .....                                | 1  |
| TRAFFIC CONTROL PLAN .....                                  | 1  |
| SIGN PANEL – TYPE 1 .....                                   | 3  |
| MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION.....    | 3  |
| RAILROAD, FULL ACTUATED CONTROLLER AND TYPE IV CABINET..... | 4  |
| RAILROAD INTERCONNECT CABLE .....                           | 6  |
| SPARE RAILROAD, FULL ACTUATED CONTROLLER, SPECIAL.....      | 7  |
| TRAFFIC SIGNAL BATTERY BACKUP SYSTEM .....                  | 7  |
| WIDE AREA VIDEO DETECTION SYSTEM COMPLETE .....             | 14 |
| CAT 5 ETHERNET CABLE .....                                  | 20 |
| REMOVAL OF LIGHTING LUMINAIRE, NO SALVAGE.....              | 20 |
| COMBINATION LIGHTING CONTROLLER.....                        | 21 |
| RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE).....          | 22 |
| RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE).....          | 23 |
| RAILROAD PERMIT APPLICATION.....                            | 24 |
| BLENDED FINELY DIVIDED MINERALS (BDE).....                  | 27 |
| COMPENSABLE DELAY COSTS (BDE) .....                         | 27 |
| DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) ..... | 30 |
| LUMINAIRES, LED (BDE) .....                                 | 39 |
| PORTLAND CEMENT CONCRETE – HAUL TIME (BDE) .....            | 47 |
| SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE).....          | 48 |
| SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....              | 48 |
| VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....             | 49 |
| WEEKLY DBE TRUCKING REPORTS (BDE).....                      | 49 |
| WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....                | 49 |
| WORKING DAYS (BDE).....                                     | 51 |
| REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES.....           | 52 |

Revised February 18, 2022

Revise Articles 1106.02(g), 1106.02(k), and 1106.02(l) to read:

“(g) Truck Mounted/Trailer Mounted Attenuators. The attenuator shall be approved for use at Test Level 3. Test Level 2 may be used for normal posted speeds less than or equal to 45 mph.

(k) Temporary Water Filled Barrier. The water filled barrier shall be a lightweight plastic shell designed to accept water ballast and be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings.

(l) Movable Traffic Barrier. The movable traffic barrier shall be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings. The barrier shall be capable of being moved on and off the roadway on a daily basis.”

**WORKING DAYS (BDE)**

Effective: January 1, 2002

The Contractor shall complete the work within **60** working days.

Revised February 18, 2022

## **REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES**

**Description.** This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

**Contract Specific Work Areas.** The excavated soil and groundwater within the work areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

### **Site 3534-1 – Agricultural Land, 3800 – 3900 blocks of 78<sup>th</sup> Avenue West, Rock Island, Rock Island County**

- All excavation in the northwest and southwest quadrants of Andalusia Road/78th Avenue (IL 92) and Centennial Expressway (IL 92): The Engineer has determined that this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

### **Site 3534-2 – Rail Road, 3600 – 3900 blocks of 78<sup>th</sup> Avenue West, Rock Island, Rock Island County**

- All excavation in the southwest and southeast quadrants of Andalusia Road/78th Avenue (IL 92) and Centennial Expressway (IL 92): The Engineer has determined that this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

### **Site 3534-4 – Vacant Land, 3600 – 3700 blocks of 78<sup>th</sup> Avenue West, Rock Island, Rock Island County**

- All excavation in the northeast quadrant of Andalusia Road/78th Avenue (IL 92) and Centennial Expressway (IL 92): The Engineer has determined that this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

### **Site 3534-5 – Harding Carbone, Inc., 3610 78<sup>th</sup> Avenue West, Rock Island, Rock Island County**

- All excavation along Andalusia Road/78th Avenue: The Engineer has determined that this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

### **Site 3534-6 – Hawkeye Real Estate, 7800 14<sup>th</sup> Street West, Rock Island, Rock Island County**

- All excavation along Andalusia Road/10th Avenue: The Engineer has determined that this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

### **Site 3534-7 – Residence, 1305 10<sup>th</sup> Avenue, Milan, Rock Island County**

- All excavation in the northwest quadrant of Andalusia Road/10th Avenue and Ridgewood Road/14<sup>th</sup> Street West: The Engineer has determined that this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

Added February 18, 2022

**Site 3534-8 – Rail Road, 1300 block of 10<sup>th</sup> Avenue West, Milan and Rock Island, Rock Island County**

- All excavation in the southwest and southeast quadrants of Andalusia Road/10<sup>th</sup> Avenue and Ridgewood Road/14<sup>th</sup> Street West: The Engineer has determined that this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

**Site 3534-9 – Village of Milan, 1223 10<sup>th</sup> Avenue West, Milan, Rock Island County**

- All excavation in the northeast quadrant of Andalusia Road/78<sup>th</sup> Avenue and Ridgewood Road/14<sup>th</sup> Street West: The Engineer has determined that this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

**Work Zones**

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites: **None.**

Additional information on the above sites collected during the Phase I Engineering process is available through the District's Environmental Studies Unit (DESU).

Added February 18, 2022