



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 25, 2022

SUBJECT FAP Route 770 (IL 128)  
Project STP-AE02(413)  
Section (116BR-2)B-1  
Moultrie County  
Contract 74434  
Item No. 77, March 11, 2022 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices
2. Revised page 7 of the Special Provisions.
3. Revised sheet 3-4, 6, and 10 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

equipment necessary to protect or reset survey markers and to adjust existing vaults. The work for furnishing and installing new survey marker vaults will be paid for according to the survey marker vault special provision.

## REMOVAL OF EXISTING SUPERSTRUCTURES

The removal and satisfactory disposal of existing structure number 070-0038 shall be according to Section 501 of the "Standard Specifications for Road and Bridge Construction" and as described in the plans. The work shall include the removal of the steel bridge rail, hot-mix asphalt wearing surface, and PCC deck beams.

All work described shall be paid for at the contract unit price per EACH for REMOVAL OF EXISTING SUPERSTRUCTURES with no additional compensation involved.

## ROAD CLOSURE

FAP 770 (IL 128) shall be closed to traffic during the rehabilitation of structure number 070-0038.

The Contractor will not be permitted to close both lanes of FAP 770 (IL 128) to all traffic prior to May 15, 2022. Prior to May 15, 2022, the Contractor will be permitted to work on pay items that can be worked on off the road or that can be completed utilizing a lane closure keeping one lane open to traffic at all times.

The Contractor shall maintain access to all field, private, and commercial entrances located inside the road closure at all times.

Failure to safely open the road on or before August 15, 2022 will result in the Contractor paying liquidated damages based on the total contact amount, per Article 108.09, for each calendar day beyond August 15, 2022.

## SEEDING, CLASS 2 (SPECIAL)

All areas disturbed during construction shall be seeded with Class 2 Seeding in accordance with Section 250 of the Standard Specifications.

All disturbed areas shall be covered with Mulch in accordance with Section 251 of the Standard Specifications. The Contractor shall use Method 1.

This work will be paid for at the contract unit price per ACRE (hectare) for SEEDING, CLASS 2 (SPECIAL), which price shall include furnishing and applying fertilizer nutrients at the rate of 90 lbs./acre (100 kg/ha) for Nitrogen, 90 lbs./acre (100 kg/ha) for Phosphorus, 90 lbs./acre (100 kg/ha) for Potassium; Agricultural Ground Limestone at the rate of 4 tons/acre (9 metric tons/ha); and Mulch at the rate of 2 tons/acre (4.5 metric tons/ha).

Revised 2-24-2022