

URBAN

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 80% FEDERAL 20% STATE	0013 80% FEDERAL 20% STATE	0021 80% FEDERAL 10% STATE 10% CITY
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	1		
	701606					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	1		
	701601					
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	1		
	701602					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	1		
	701701					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	1		
	701801					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	25	25		
70107007	PAVEMENT MARKING BLACKOUT TAPE, 7"	FOOT	389	389		
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	56	56		
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	47760	47760		
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	15920	15920		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2025	2025		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 80% FEDERAL 20% STATE	0013 80% FEDERAL 20% STATE	0021 80% FEDERAL 10% STATE 10% CITY
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1012.5	1012.5		
70600240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	1	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1706	1706		
70600340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	1	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24589	24589		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5377	5377		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1452	1452		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	160	160		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	368	368		
* 78004630	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - LINE 6"	FOOT	6767	6767		
* 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	1368	1368		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	573	573		
* 78200020	CURB REFLECTORS	EACH	579	579		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	573	573		
* 81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	91		91	

\* SPECIALTY ITEM

△ REVISED 2-28-2022

REV. - MS

MODEL: D:\pilot\pilotroom.dwg; ILLINOIS.GOV\PILOT\DOT\Documents\DOT\_Offices\District 3\Projects\74637\CADD\DATA\CAD\Sheets\74637-500.dgn

USER NAME = steffenmk	DESIGNED - LMH	REVISED -
DRAWN - LMH	CHECKED -	REVISED -
PLOT SCALE = 100.0000' / in.	DATE - \$DATE\$	REVISED -
PLOT DATE = 5/14/2021		

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NO SCALE SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
710	*	MACON	84	5
			CONTRACT NO. 74637	
(ILLINOIS FED. AID PROJECT)				

\*(48Z2&3,50Z2&3,50R)RS-3