

SUMMARY OF QUANTITIES

US 14 US 41
100% STATE URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				0014 FAP 341	0041 FAP 348
42001165	BRIDGE APPROACH PAVEMENT	SO YD	138	138	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	88	88	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	175	175	
44000100	PAVEMENT REMOVAL	SO YD	41	41	
44000600	SIDEWALK REMOVAL	SO FT	175	175	
50300300	PROTECTIVE COAT	SO YD	1,542	1,542	
50900105	ALUMINUM RAILING, TYPE L	FOOT	25.5		25.5
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2	
67100100	MOBILIZATION	L SUM	1.0	1.0	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.0		1.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1,766	1,766	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	575	575	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	575	575	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	146	146	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,015	3,015	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	855	855	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	337	337	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	123	123	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	452	452	
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	54	54	
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	46	46	
78300100	PAVEMENT MARKING REMOVAL	SO FT	2,219	2,219	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL) <small>(TYPE III -</small>	L SUM	1.0	1.0	
X7030025	WET REFLECTIVE TEMPORARY TAPE/LETTERS AND SYMBOLS	SO FT	438	438	
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	3,987	3,987	
Z0004552	APPROACH SLAB REMOVAL	SO YD	184	184	
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	63	63	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	2		2
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	4	4	
Z0030360	IMPACT ATTENUATORS, RELOCATE (SEVERE USE), TEST LEVEL 3	EACH	2	2	
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	55	55	

* SPECIALTY ITEMS

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE

FILE NAME = G:\p\proj\2102195_201001\2102195_201001\CADD\Civil\Sheet\071410-05-S00.dgn