

**GENERAL NOTES**  
(Revised May 13, 2009)

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.


ONLY THOSE TREES DESIGNATED BY THE ENGINEER OR LISTED IN THE TREE REMOVAL SCHEDULE SHALL BE REMOVED. THE CONTRACTOR SHALL PROTECT ALL REMAINING TREES FROM DAMAGE DUE TO HIS OPERATIONS.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

**COMMITMENT:**

TO COMPLY WITH THE ENVIRONMENTAL CLEARANCE REQUIREMENTS ANY DISTURBED EARTH SHALL NOT BE REMOVED FROM THE JOB SITE.



GPS COORDINATES OF STA. 57+65.82  
N 41°38.516'  
W 88°29.997'

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
DISTRICT THREE

PREPARED BY: Deen Brown  
DISTRICT STUDIES & PLANS ENGINEER

DATE: October 27, 2010

EXAMINED BY: Richard L. ...  
DISTRICT CONSTRUCTION ENGINEER

Wayne L. Phillips  
DISTRICT MATERIALS ENGINEER

Ronald H. ...  
DISTRICT OPERATIONS ENGINEER

FILE NAME =	USER NAME = schwankeg	DESIGNED -	REVISED -
ca\pw_work\pwsdot\schwankeg\10234950\388A66-aht-cover.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0000 / IN.		CHECKED -	REVISED -
PLOT DATE = Oct 27, 2010 - 10:02:29 AM		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

**GENERAL NOTES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNT	TOTAL SHEETS	SHEET NO.
319	(47-3)	KENDALL	8	2
CONTRACT NO. 66A66				
ILLINOIS FED. AID PROJECT				