

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	1919.2B	COOK	119	13
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
			CONTRACT 60371	

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30			LENGTH (METER)		
STA		STA		LENGTH (METER)	
115 TH STREET					
2+261.0	LT	2+317.5	LT	56.5	
2+261.0	RT	2+322.1	RT	61.1	
2+346.0	LT	2+348.5	LT	2.5	
2+345.7	RT	2+348.5	RT	2.8	
2+417.4	LT	2+419.8	LT	2.4	
2+417.4	RT	2+420.4	RT	3.0	
2+443.2	LT	2+519.0	LT	76.3	
2+446.5	RT	2+479.1	RT	32.8	
2+479.1	RT	2+519.0	RT	40.3	
MARSHFIELD AVENUE					
4+115.0	LT	4+124.4	LT	14.8	
4+115.0	RT	4+119.0	RT	4.0	
4+119.0	RT	4+121.9	RT	4.8	
4+139.5	LT	4+155.0	LT	22.2	
4+141.3	RT	4+144.3	RT	4.8	
4+144.3	RT	4+155.0	RT	10.1	
ASHLAND AVENUE					
6+112.0	LT	6+119.3	LT	7.3	
6+112.0	RT	6+115.3	RT	3.3	
6+119.3	LT	6+122.5	LT	4.8	
6+115.3	RT	6+124.7	RT	14.5	
6+141.5	LT	6+144.5	LT	4.6	
6+140.0	RT	6+148.3	RT	13.0	
6+144.5	LT	6+152.5	LT	7.7	
6+148.3	RT	6+152.5	RT	4.3	
TOTAL				=	398

SHORT-TERM PAVEMENT MARKING						
STA	OFFSET		STA	OFFSET	LENGTH M	TOT LENGTH M
100 MM						
115TH STREET						
2+134.0	3.20	RT	2+322.0	3.90	188.00	SKIP/DASH 18.80
2+261.0	0.00		2+324.1	0.00	63.10	DBL YELLOW 6.31
2+291.7	0.00		2+324.1	0.00	32.40	DBL YELLOW 3.24
2+257.8	2.90	LT	2+322.0	4.50	64.20	SKIP/DASH 6.42
2+443.5	4.10	RT	2+649.0	3.05	205.50	SKIP/DASH 20.55
2+443.5	4.10	LT	2+649.0	3.05	205.50	SKIP/DASH 20.55
2+442.2	0.00		2+511.7	0.00	69.50	DBL YELLOW 6.95
2+442.2	0.00		2+649.0	0.00	206.80	DBL YELLOW 20.68
2+349.0	5.02	LT	2+416.5	4.99	67.50	SKIP/DASH 6.75
2+349.0	4.93	RT	2+416.5	4.93	67.50	SKIP/DASH 6.75
2+351.0	1.39	RT	2+412.0	1.39	61.50	DBL YELLOW 6.15
2+343.7	8.25	LT	2+422.1	8.25	78.40	SOLID WHITE 7.84
2+343.7	8.25	RT	2+422.1	8.25	78.40	SOLID WHITE 7.84
MARSHFIELD AVENUE						
4+115.0	1.90	RT	4+120.0	1.90	5.00	SKIP/DASH 0.50
4+115.0	1.90	LT	4+120.0	1.90	5.00	SKIP/DASH 0.50
4+144.0	1.70	LT	4+215.0	1.70	71.00	SKIP/DASH 7.10
4+142.0	1.90	RT	4+209.3	5.50	67.30	SOLID WHITE 6.73
ASHLAND AVENUE						
6+076.6	1.25	LT	6+117.5	1.95	40.90	SKIP/DASH 4.09
6+076.6	2.35	RT	6+117.5	1.65	40.90	SKIP/DASH 4.09
6+144.0	1.56	LT	6+152.7	1.82	8.66	SKIP/DASH 0.87
6+144.0	2.04	RT	6+152.7	1.78	8.66	SKIP/DASH 0.87
6+085.2	8.29	RT	6+118.9	7.09	33.70	SOLID WHITE 3.37
TOTAL				=	176	

150 MM			
STA	OFFSET		TOT AREA SQ M
115TH STREET			
2+349.0	1.66	LT	21.50
2+391.5	1.67	RT	25.00
2+370.5	1.66	LT	20.00
2+371.5	1.67	RT	20.00
TOTAL = 176			
TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS			
STA	OFFSET	LETTER	TOT AREA SQ M
STAGE I			
115TH STREET			
2+358.7		RT	1.47
2+366.5		ONLY	2.13
2+399.0		ONLY	2.13
2+407.1		LT	1.47
2+272.5		RT	0.33
2+272.5		LT	0.33
TOTAL = 8			

TEMPORARY PAVEMENT MARKING - LINE 100 MM									
STA	OFFSET		STA	OFFSET	LENGTH M	LINE TYPE	TOT LENGTH M		
STAGE I									
115TH STREET									
2+261.0	2.80	LT	2+330.0	2.30	69.00	SOLID WHITE	69.00		
2+341.0	2.00	LT	2+426.0	2.00	85.00	SOLID WHITE	85.00		
2+437.0	2.00	LT	2+519.4	0.00	82.42	SOLID WHITE	82.42		
2+346.0	6.70	RT	2+419.5	3.66	73.56	DBLE YELLOW	147.13		
2+446.5	4.40	RT	2+519.4	4.10	72.90	DBLE YELLOW	145.80		
2+261.0	0.30	RT	2+315.0	3.67	47.11	SOLID YELLOW	47.11		
2+261.0	3.30	RT	2+315.0	3.67	47.00	SOLID YELLOW	47.00		
2+315.0	3.65	RT	2+346.0	4.22	31.01	DOTTED	7.75		
2+419.5	3.70	RT	2+446.5	4.18	27.00	DOTTED	6.75		
MARSHFIELD AVENUE									
4+134.0	7.34	LT	4+155.0	5.40	21.09	SOLID WHITE	21.09		
4+146.0	1.78	LT	4+155.0	1.78	9.00	SKIP/DASH	2.22		
4+134.0	3.90	RT	4+155.0	2.00	21.09	SOLID YELLOW	21.09		
ASHLAND AVENUE									
6+134.0	7.34	RT	6+152.7	5.50	18.75	SOLID WHITE	18.75		
6+112.2	3.72	RT	6+119.0	3.72	6.78	SKIP/DASH	1.67		
6+112.2	0.50	RT	6+119.0	0.60	6.78	SOLID YELLOW	6.78		
6+134.0	3.16	LT	6+152.7	0.60	18.83	SOLID YELLOW	18.83		
6+112.2	0.50	RT	6+119.0	0.50	6.78	SOLID WHITE	6.78		
6+112.2	2.50	LT	6+119.0	2.50	6.78	SKIP/DASH	1.67		
STAGE II									
115 TH STREET									
2+261.0	3.30	RT	2+327.0	0.00	70.00	SOLID WHITE	70.00		
2+442.0	0.00		2+519.4	0.00	84.00	SOLID WHITE	84.00		
MARSHFIELD AVENUE									
4+115.0	5.60	LT	4+132.0	9.50	17.44	SOLID WHITE	17.44		
4+115.0	0.20	RT	4+132.0	4.00	17.42	SOLID YELLOW	17.42		
ASHLAND AVENUE									
6+112.2	7.70	RT	6+130.0	11.30	18.14	SOLID WHITE	18.14		
6+112.2	0.00		6+130.0	4.50	18.34	SOLID YELLOW	18.34		
6+112.2	3.75	RT	6+119.0	3.75	6.78	SKIP/DASH	1.67		
TOTAL				=	964				

TEMPORARY PAVEMENT MARKING - LINE 150 MM									
STA	OFFSET		STA	OFFSET	LENGTH M	LINE TYPE	TOT LENGTH M		
STAGE I									
115TH STREET									
2+346.0	3.65	RT	2+370.0	3.65	24.00	SOLID WHITE	24.00		
2+370.0	3.65	RT	2+395.0	3.65	25.00	SKIP/DASH	6.25		
2+370.0	6.71	RT	2+395.0	6.71	25.00	SKIP/DASH	6.25		
2+395.0	6.71	RT	2+419.5	6.71	24.50	SOLID WHITE	24.50		
TOTAL				=	61				
TEMPORARY PAVEMENT MARKING - LINE 400 MM									
STA	OFFSET		STA	OFFSET	LENGTH M	LINE TYPE	TOT LENGTH M		
115TH STREET									
2270.2	1.5	LT	2276.1	0.6	6.2	SOLID WHITE	6.2		
2270.2	0.6	RT	2276.1	1.5	6.2	SOLID WHITE	6.2		
TOTAL				=	12				

WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS									
STA	OFFSET		STA	OFFSET	LENGTH M	LINE TYPE	TOT LENGTH M	LETTER	TOT AREA SQ M
STAGE II & STAGE III									
115TH STREET									
2+280.7		LT				R	0.33		
2+280.7		LT				R	0.33		
2+359.8		LT				LT ARROW	1.47		
2+367.2		LT				ONLY	2.13		
2+399.0		LT				ONLY	2.13		
2+407.0		LT				LT ARROW	1.47		
STAGE III									
115 TH STREET									
2+397.9		RT				ONLY	2.13		
2+404.9		RT				LT ARROW	1.47		
TOTAL				=	11				

TEMPORARY PAVEMENT MARKING - LINE 600 MM									
STA	OFFSET		STA	OFFSET	LENGTH M	LINE TYPE	TOT LENGTH M		
STAGE I-A									
115 TH STREET									
2+264.9	2.55	LT			0.50	RT	3.05	SOLID WHITE	3.05
2+280.0	1.60	LT			1.45	RT	3.05	SOLID WHITE	3.05
2+315.0	3.95	RT			7.00	RT	3.05	SOLID WHITE	3.05
2+346.0	0.60	RT			3.70	RT	3.10	SOLID WHITE	3.10
2+350.0	3.70	RT			6.80	RT	3.10	SOLID WHITE	3.10
2+415.0	3.66	RT			6.76	RT	3.10	SOLID WHITE	3.10
2+419.5	6.76	RT			9.86	RT	3.10	SOLID WHITE	3.10
2+446.5	1.31	RT			4.36	RT	3.05	SOLID WHITE	3.05
MARSHFIELD AVENUE									
4+146.0	5.10	LT			1.00	RT	6.10	SOLID WHITE	6.10
ASHLAND AVENUE									
6+119.0	0.20	RT			7.50	RT	7.30	SOLID WHITE	7.30
STAGE I-B									
115 TH STREET									
2+349.0	0.00				3.10	RT	3.10	SOLID WHITE	3.10
2+353.0	3.10	RT			6.20	RT	3.10	SOLID WHITE	3.10
ASHLAND AVENUE									
6+119.0	6.60	RT			0.50	RT	6.10	SOLID WHITE	6.10
TOTAL				=	50				

WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III (LINE 150 MM)									
STA	OFFSET		STA	OFFSET	LENGTH M	LINE TYPE	TOT LENGTH M		
STAGE II									
115TH STREET									
2+346.0	6.55	LT	2+370.0	6.55	24.00	SOLID WHITE	24.00		
2+370.0	6.55	LT	2+395.0	6.55	25.00	SKIP/DASH	6.25		
2+370.0	3.50	LT	2+395.0	3.50	25.00	SKIP/DASH	6.25		
2+395.0	3.50	LT	2+419.5	3.50	24.50	SOLID WHITE	24.50		
TOTAL				=	122				

WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III (LINE 300 MM)									
STA	OFFSET		STA	OFFSET	LENGTH M	LINE TYPE	TOT LENGTH M		
STAGE II & STAGE III									
115TH STREET									
2+277.5	3.75	LT	2+283.9	6.38	6.54	SOLID WHITE	6.54		
2+277.5	6.16	LT	2+283.9	3.97	6.54	SOLID WHITE	6.54		
TOTAL				=	13				