SHEET \$4 OF \$27

TOTAL SHEET SHEET NO. F.A.I. RTE. COUNTY SECTION COOK 90 1213B-1 94 51 FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

CONTRACT NO. 60640

When "A" is 1.067m or less, the temporary concrete barrier shall be anchored to the new slab according to Detail I or Detail II. No anchorage is required when "A" is greater than 1.067m.

See Detail 1 slab for 25mm¢ x 280mm dowel or Detail II.

NEW SLAB

Stage construction line

Drill 3-30mm \$\phi\$ Holes in existing

Stage removal line

Temporary Concrete Barrier

See Standard 704001

bars. Traffic side only. Cost included

with Temporary Concrete Barrier.

572

572

EXISTING DECK BEAM

## NOTES

Detail I - With Bar Splicer or Couplers: Connect one (1) 25x180x250 steel P2 to the top layer of couplers with 2- 16mm φ bolts screwed to coupler at approximate © of each barrier panel.

Detail II - With Extended Reinforcement Bars: Connect one (1) 25x180x250 steel P to the concrete slab or concrete wearing surface with 2- 16mm  $\phi$ Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate © of each barrier panel.

Cost of anchorage is included with Temporary Concrete Barrier. The 25x180x250 plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready to be placed.


## SECTIONS THRU SLAB OR DECK BEAM

EXISTING SLAB


\*\*\*Dimension shown is minimum required embedment into concrete. If hot-mix asphalt wearing surface is present, minimum embedment shall be in addition to wearing surface depth.

\*\*\*\*If existing deck beam is to remain in place after stage construction,

embedment shall only be into wearing surface and not into existing deck beam concrete.



DETAIL I



DETAIL II

→ ¢ 22mm ¢ Holes \*£ 25 x 40 Notch

250

Top bars

75

spacing

75

## STEEL RETAINER P 25 x 180 x 250

\*Required only with Detail II

	ILLINOIS DEPARTMENT OF TRANSPORTATION
provide	TEMPORARY CONCRETE BARRIER
ood blocks tirect contact	REVISIONS FOR STAGE CONSTRUCTION
in eer comider	NAME DATE CENTRAL AVENUE (FAU RTE. 2798) OVER
	INTERSTATE 90 (KENNEDY EXPWY.) & C.T.A
	F.A.I. RTE. 90 SECTION: 1213B-1
	COOK COUNTY STATION 1+000.000 STRUCTURE NO. 016-0659
	SCALE: NONE DRAWN BY: D.L./F.M.
	DATE: JANUARY 16, 2009 CHECKED BY: B.N.S./J.C.
	CHRISTIAN-ROGE & ASSOC., INC.

\*\*Wood blocks may be omitted when required to pr minimum stage traffic lane width. When the wood are omitted, the concrete barrier shall be in dire with the steel retainer plate.