

SUMMARY OF QUANTITIES			URBAN 1001.FED. TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000- 2A	LIGHTING Y030-1E	BRIDGE X271-2A
M5090520	BRIDGE FENCE RAILING	METER	135		135	
M5120900	TEMPORARY SHEET PILING	SQ M	182		182	
M5200225	PREFORMED JOINT STRIP SEAL	METER	24.1		24.1	
M5510010	STORM SEWER REMOVAL 150 MM	METER	9	9		
M5510015	STORM SEWER REMOVAL 200 MM	METER	7	7		
M5510020	STORM SEWER REMOVAL 250 MM	METER	2	2		
M5870300	CONCRETE SEALER	SQ M	46		46	
M5900200	EPOXY CRACK INJECTION	METER	4.0		4.0	
M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	48		48	
M6011100	PIPE UNDERDRAINS FOR STRUCTURES 100 MM	METER	17		17	
M6020180	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 23 FRAME AND GRATE	EACH	5	5		
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	115	115		
M6640100	CHAIN LINK FENCE, 1.2 METER	METER	55	55		
M6641930	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	METER	20	20		
M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	360	360		
M7030550	PAVEMENT MARKING TAPE, TYPE III 200MM	METER	260	260		
M7030580	PAVEMENT MARKING TAPE, TYPE III 600MM	METER	9	9		
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	95	95		
M7040100	TEMPORARY CONCRETE BARRIER	METER	350	350		
M7040200	RELOCATE TEMPORARY CONCRETE BARRIER	METER	70	70		
* M7200100	SIGN PANEL - TYPE 1	SQ M	0.7	0.7		
* M7240310	REMOVE SIGN PANEL - TYPE 1	SQ M	0.3	0.3		
* M7240710	RELOCATE SIGN PANEL - TYPE 1	SQ M	1.2	1.2		
* M7280100	TELESCOPING STEEL SIGN SUPPORT	METER	6.4	6.4		
* M7290100	METAL POST - TYPE A	METER	7.6	7.6		
* M7290200	METAL POST - TYPE B	METER	4.1	4.1		
* M7800105	THERMOPLASTIC PAVEMENT MARKING - LINE 100 MM	METER	32	32		
* M7800115	THERMOPLASTIC PAVEMENT MARKING - LINE 150 MM	METER	90	90		
* M7800140	THERMOPLASTIC PAVEMENT MARKING - LINE 600 MM	METER	15	15		
* M7800405	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 100 MM	METER	140	140		
* M8080110	TEMPORARY WOOD POLE, 12.19 METER, CLASS 4	EACH	2	2		
* M8130120	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 150MM X 150MM X 100MM	EACH	8	8		

\*SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 1001.FED. TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000- 2A	LIGHTING Y030-1E	BRIDGE X271-2A
* M8130185	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 300MM X 250MM X 150MM	EACH	4	4		
* M8130223	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 400MM X 350MM X 150MM	EACH	4	4		
* M8160400	UNIT DUCT, WITH 3-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (EPR-TYPE RHW), 30MM DIA., POLYETHYLENE	METER	185	185		
* M8170425	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	METER	1,040	1,040		
* M8180143	AERIAL CABLE, 3-1/C NO. 4, ALUMINUM, WITH MESSENGER WIRE	METER	250	250		
* M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	165	165		
* MX030208	CONDUIT ATTACHED TO STRUCTURE, 65MM DIA. GALVANIZED STEEL, PVC COATED	METER	25	25		
* MX030243	CONDUIT ATTACHED TO STRUCTURE, 75MM DIA. GALVANIZED STEEL, PVC COATED	METER	20	20		
* MX030300	CONDUIT ATTACHED TO STRUCTURE, 25MM DIA. GALVANIZED STEEL, PVC COATED	METER	200	200		
MX032178	TEMPORARY INFORMATION SIGNING	SQ M	5	5		
MX033468	STORM SEWER, DUCTILE IRON PIPE, TYPE 2, 200 MM	METER	30	30		
MX033694	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 125 MM)	SQ M	38		38	
* MX873065	ELECTRIC CABLE IN CONDUIT, 600V (EPR TYPE RHW) 3-1/C NO. 4 AND #6 GROUND	METER	30	30		
MZ017205	DOWEL BARS 38MM	EACH	84	84		
* X0322424	TEMPORARY UNDERPASS LIGHTING INSTALLATION AND REMOVAL	L SUM	1	1		
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	22	22		
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6	6		
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	4	4		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1		
X7013820	TRAFFIC CONTROL SURVEILLANCE (EXPRESSWAYS)	CAL DAY	180	180		
* XX004964	UNDERPASS LIGHTING REMOVAL	L SUM	1	1		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0018800	DRAINAGE SYSTEM	L SUM	1	1		
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0075310	TIE BARS 3/4"	EACH	84	84		
* X0326320	REMOVE, GROUND MOUNT, AND RE-ERECT OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	1	1		
MX033762	STORM SEWER, DUCTILE IRON PIPE, TYPE 2, 250 MM	METER	3	3		
MX033761	ANCHOR BOLT, M30	EACH	24	24		

© 20076600 TRAINERS

HOURLY 500 500

© 2080

FAI 57/INTERSTATE 57  
125TH STREET OVER I-57  
SUMMARY OF QUANTITIES

F.A.I. RTE. 57	SECTION 1818.3B-R	COUNTY COOK	TOTAL SHEETS 58	SHEET NO. 5
CONTRACT NO. 60862			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT	

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCALE: SHEET NO. OF SHEETS STA. TO STA.

**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
6507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = dmorris	DESIGNED -	REVISED -
PLOT SCALE = 1:9234 m / MM.	DRAWN -	REVISED -
PLOT DATE = 1/16/2009	CHECKED -	REVISED -
	DATE = 1/16/2009	REVISED -

