

**CONTRACT 60C08
CLASS D PATCHING SUMMARY**

SCHEDULE	CLASS D, 10"			HMA RMOV PAT 4 (SY)	HMA RMOV PAT 10 (SY)	HMA REPL OVER PATCH (TON)
	TYPE II (SY)	TYPE III (SY)	TYPE IV (SY)			
EASTBOUND MAINLINE	57		87		170	95
WESTBOUND MAINLINE	161		27		240	135
EASTBOUND RAMPS	29		36	75		17
STONY ISLAND BRIDGES	181	24	89			
EASTBOUND STONY ISLAND FEEDER RAMPS (SHEET 2 OF 9)	492	117	1,034			
WESTBOUND STONY ISLAND FEEDER RAMPS (SHEET 2 OF 9)	149	184	1,395			
TOTAL	1,069	325	2,668	75	410	247

**CONTRACT 60C08
MAINLINE CLASS D PATCHING SCHEDULE**

EASTBOUND MAINLINE

PATCH NUMBER	STATION	LANE NUMBER	LENGTH (FT)	WIDTH (FT)	LANE 1			LANE 2			LANE 3			TOTAL					
					CLASS D, 10"		HMA	CLASS D, 10"		HMA	CLASS D, 10"		HMA	CLASS D, 10"		HMA	CLASS D, 10"		HMA
					TYPE II (SY)	TYPE IV (SY)	RMOV PAT 10 (SY)	REPL OVER PATCH (TON)	TYPE II (SY)	TYPE IV (SY)	RMOV PAT 10 (SY)	REPL OVER PATCH (TON)	TYPE II (SY)	TYPE IV (SY)	RMOV PAT 10 (SY)	REPL OVER PATCH (TON)	TYPE II (SY)	TYPE IV (SY)	RMOV PAT 10 (SY)
1E	120+99	1	4	12	5.4		8.0	4.5					5.4		8.0	4.5			
2E	120+99	2	4	12					5.4		8.0	4.5	5.4		8.0	4.5			
3E	120+99	3	4	12									5.4		8.0	4.5			
4E	180+46	1	6	12	8.0		10.7	6.0					8.0		10.7	6.0			
5E	180+46	2	6	12					8.0		10.7	6.0	8.0		10.7	6.0			
6E	181+00	1	40	12		53.4	56.0	31.4						53.4	56.0	31.4			
7E	190+61	1	25	12		33.4	36.0	20.2						33.4	36.0	20.2			
8E	201+30	1	6	12	8.0		10.7	6.0					8.0		10.7	6.0			
9E	201+30	2	6	12					8.0		10.7	6.0	8.0		10.7	6.0			
10E	373+62	3	6	12						8.0	10.7	6.0	8.0		10.7	6.0			
SUBTOTAL EASTBOUND														56.2	86.8	169.3	94.8		
ROUNDED SUBTOTAL EASTBOUND														57	87	170	95		

WESTBOUND MAINLINE

PATCH NUMBER	STATION	LANE NUMBER	LENGTH (FT)	WIDTH (FT)	LANE 1			LANE 2			LANE 3			TOTAL					
					CLASS D, 10"		HMA	CLASS D, 10"		HMA	CLASS D, 10"		HMA	CLASS D, 10"		HMA	CLASS D, 10"		HMA
					TYPE II (SY)	TYPE IV (SY)	RMOV PAT 10 (SY)	REPL OVER PATCH (TON)	TYPE II (SY)	TYPE IV (SY)	RMOV PAT 10 (SY)	REPL OVER PATCH (TON)	TYPE II (SY)	TYPE IV (SY)	RMOV PAT 10 (SY)	REPL OVER PATCH (TON)	TYPE II (SY)	TYPE IV (SY)	RMOV PAT 10 (SY)
1W	163+34	1	8	12	10.7		13.3	7.5					10.7		13.3	7.5			
2W	163+34	2	8	12					10.7		13.3	7.5	10.7		13.3	7.5			
3W	186+75	1	6	12	8.0		10.7	6.0					8.0		10.7	6.0			
4W	186+75	2	6	12					8.0		10.7	6.0	8.0		10.7	6.0			
5W	187+28	1	6	12	8.0		10.7	6.0					8.0		10.7	6.0			
6W	187+28	2	6	12					8.0		10.7	6.0	8.0		10.7	6.0			
7W	199+76	1	4	12	5.4		8.0	4.5					5.4		8.0	4.5			
8W	199+76	2	4	12					5.4		8.0	4.5	5.4		8.0	4.5			
9W	217+27	1	6	12	8.0		10.7	6.0					8.0		10.7	6.0			
10W	217+27	2	6	12					8.0		10.7	6.0	8.0		10.7	6.0			
11W	247+23	1	6	12	8.0		10.7	6.0					8.0		10.7	6.0			
12W	247+23	2	6	12					8.0		10.7	6.0	8.0		10.7	6.0			
13W	247+23	3	6	12									8.0		10.7	6.0			
14W	377+37	1	6	12	8.0		10.7	6.0					8.0		10.7	6.0			
15W	377+37	2	6	12					8.0		10.7	6.0	8.0		10.7	6.0			
16W	377+37	3	6	12									8.0		10.7	6.0			
17W	387+55	3	20	12						26.7	29.3	16.4	8.0	26.7	29.3	16.4			
18W	433+50	1	8	12	10.7		13.3	7.5					10.7		13.3	7.5			
19W	433+50	2	8	12					10.7		13.3	7.5	10.7		13.3	7.5			
20W	433+50	3	8	12						10.7	13.3	7.5	10.7		13.3	7.5			
SUBTOTAL WESTBOUND														160.3	26.7	240.0	134.4		
ROUNDED SUBTOTAL WESTBOUND														161	27	240	135		

**CONTRACT 60C08
RAMP CLASS D PATCHING SCHEDULE**

EASTBOUND RAMPS

PATCH NUMBER	LOCATION	LENGTH (FT)	WIDTH (FT)	CLASS D, 10"		HMA RMOV PAT 4 (SY)	HMA REPL OVER PATCH (TON)
				TYPE II (SY)	TYPE IV (SY)		
R4	STONY ISLAND AVE EXIT RAMP	20	16		35.6	39.1	8.8
R5	DOTY AVE - RAMP A	10	12	13.4		16.0	3.6
R6	STONY ISLAND AVE ENT. RAMP	6	22	14.7		19.6	4.4
SUBTOTAL EASTBOUND RAMPS				28.1	35.6	74.7	16.7
ROUNDED SUBTOTAL EASTBOUND RAMPS				29	36	75	17

CONTRACT 60C08

STONY ISLAND BRIDGES- CLASS D PATCHING SCHEDULE

EASTBOUND STONY ISLAND

NUMBER	LOCATION	LENGTH (FT)	WIDTH (FT)	CLASS D, 10"		
				TYPE II (SY)	TYPE III (SY)	TYPE IV (SY)
BR 1	LN 1 AND LT SHDR AT BRIDGE OVER I-94 (WEST END)	4	71			31.6
BR 2	LN 2 AND RT SHDR AT BRIDGE OVER I-94 (WEST END)	4	71			31.6
BR 3	LN1 AND LT SHDR AT BRIDGE OVER I-94 (EAST END)	4	52		23.1	
BR 4	LN 2 AND RT SHDR AT BRIDGE OVER I-94 (EAST END)	4	58			25.8
BR 5	LN 1 AND LT SHDR AT BRIDGE OVER WOODLAWN (WEST END)	4	22	9.8		
BR 6	LN 2 AND RT SHDR AT BRIDGE OVER WOODLAWN (WEST END)	4	21	9.3		
BR 7	LN 1 AND LT SHDR AT BRIDGE OVER WOODLAWN (EAST END)	4	22	9.8		
BR 8	LN 2 AND RT SHDR AT BRIDGE OVER WOODLAWN (EAST END)	4	20	8.9		
BR 9	LN 1 AND LT SHDR AT BRIDGE OVER DORCHESTER (WEST END)	4	21	9.3		
BR 10	LN 2 AND RT SHDR AT BRIDGE OVER DORCHESTER (WEST END)	4	23	10.2		
BR 11	LN 1 AND LT SHDR AT BRIDGE OVER DORCHESTER (EAST END)	4	22	9.8		
BR 12	LN 2 AND RT SHDR AT BRIDGE OVER DORCHESTER (EAST END)	4	22	9.8		
SUB TOTAL (EB)				76.9	23.1	
ROUNDED				77	24	89

WESTBOUND STONY ISLAND

NUMBER	LOCATION	LENGTH (FT)	WIDTH (FT)	CLASS D, 10"		
				TYPE II (SY)	TYPE III (SY)	TYPE IV (SY)
BR 13	LN 1 AND LT SHDR AT BRIDGE OVER WOODLAWN (WEST END)	4	18	8.0		
BR 14	LN 2 AND RT SHDR AT BRIDGE OVER WOODLAWN (WEST END)	4	22	9.8		
BR 15	LN 1 AND LT SHDR AT BRIDGE OVER WOODLAWN (EAST END)	4	20	8.9		
BR 16	LN 2 AND RT SHDR AT BRIDGE OVER WOODLAWN (EAST END)	4	22	9.8		
BR 17	LN 1 AND LT SHDR AT BRIDGE OVER DORCHESTER (WEST END)	4	18	8.0		
BR 18	LN 2 AND RT SHDR AT BRIDGE OVER DORCHESTER (WEST END)	4	28	12.4		
BR 19	LN 1 AND LT SHDR AT BRIDGE OVER DORCHESTER (WEST END)	4	18	8.0		
BR 20	LN 2 AND RT SHDR AT BRIDGE OVER DORCHESTER (EAST END)	4	31	13.8		
BR 21	LT SHDR AND HALF RAMP PVT. AT FLYOVER RAMPB (WEST END)	4	14	6.2		
BR 22	RT SHDR AND HALF RAMP PVT. AT FLYOVER RAMP B (WEST END)	4	14	6.2		
BR 23	LT SHDR AND HALF RAMP PVT. AT FLYOVER RAMPB (EAST END)	4	14	6.2		
BR 24	RT SHDR AND HALF RAMP PVT. AT FLYOVER RAMP B (EAST END)	4	14	6.2		
SUB TOTAL (EB)				103.5		
ROUNDED				104		
TOTAL				181	24	89