

**CONTRACT 60C08  
RESURFACING SCHEDULE**

**EASTBOUND**

LOCATION		POLYMERIZED HMA SURFACE COURSE, SMA, N80	HMA SURFACE COURSE, MIX "D", N70	HMA BINDER COURSE, IL- 19, N70	HMA SURFACE REMOVAL, 4"	HMA SURFACE REMOVAL, 2"	DESCRIPTION
STA	STA	(TON)	(TON)	(TON)	(SY)	(SY)	
118+00	119+10		13.7			122.2	OUTSIDE SHOULDER
120+39	139+11		174.7			1,560.0	OUTSIDE SHOULDER
145+00	146+06		13.2			117.8	OUTSIDE SHOULDER
148+48	160+14		101.6			906.9	OUTSIDE SHOULDER
162+65	173+00		123.4			1,102.2	OUTSIDE SHOULDER
180+12	187+23		88.5			790.0	OUTSIDE SHOULDER
189+90	220+00		374.6			3,344.4	OUTSIDE SHOULDER
220+00	254+70		386.3			3,449.5	OUTSIDE SHOULDER
256+60	265+46		132.3			1,181.3	OUTSIDE SHOULDER
267+72	276+83		104.3			931.1	OUTSIDE SHOULDER
278+76	366+38		1,021.1			9,117.0	OUTSIDE SHOULDER
367+66	370+72		59.0			527.0	OUTSIDE SHOULDER
371+58	377+64		78.6			701.8	OUTSIDE SHOULDER
379+00	426+80		684.9			6,115.5	OUTSIDE SHOULDER
429+92	433+60		36.6			327.1	OUTSIDE SHOULDER
118+00	119+00		10.0			88.9	INSIDE SHOULDER
120+39	139+11		174.7			1,560.0	INSIDE SHOULDER
145+00	160+14		160.1			1,429.9	INSIDE SHOULDER
162+65	172+99		96.5			861.7	INSIDE SHOULDER
180+12	187+28		53.9			481.1	INSIDE SHOULDER
189+90	207+63		166.9			1,489.8	INSIDE SHOULDER
220+00	365+00		1,088.9			9,722.2	INSIDE SHOULDER
GORE AREAS			531.3			4,744.0	
118+00.0	172+99.2	2,474.7				18,331.2	MAINLINE
180+12.1	187+32.7	259.4				1,921.6	MAINLINE
189+90.7	433+60.0	10,007.8				74,131.5	MAINLINE
TAPERED LANES		587.2				4,349.9	MAINLINE
111TH ST RAMPS			514.6	661.6	5,250.9		
115th ST RAMPS			424.3	545.5	4,329.6		RAMP AREA
130th ST RAMPS			286.6	368.5	2,924.9		RAMP AREA
DOTY AVE RAMPS			95.9	123.3	978.4		RAMP AREA
RAMP B- C			360.2	463.2	3,675.9		
DEDUCTIONS FOR BUTT JOINTS				(73.1)			
SUBTOTAL		13,329.1	7,356.8	2,089.0	17,159.7	149,405.6	
ROUNDED SUBTOTAL		13,330	7,357	2,090	17,160	149,406	

CONTINUED NEXT SHEET

**CONTRACT 60C08**

FILE NAME = D:\60C08-014-SCHEDULE.dgn	USER NAME = dvoznarski	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>BISHOP FORD EXPRESSWAY (I-94) SCHEDULES OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
PLOT SCALE = N/A	DRAWN - DMW	REVISED -	94			K0312-708W, ETC. & 1315RS-4	COOK	167	14			
PLOT DATE = 2/6/2009	CHECKED -	REVISED -	SCALE: N/A			SHEET NO. 3 OF 9 SHEETS		STA. TO STA.		CONTRACT NO. 60C08		
	DATE - 2/6/2009	REVISED -	FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT						