

**CONTRACT 60C08
RESURFACING SCHEDULE**

WESTBOUND

LOCATION		POLYMERIZED HMA SURFACE COURSE, SMA, N80	HMA SURFACE COURSE, MIX "D", N70	HMA BINDER COURSE, IL- 19, N70	HMA SURFACE REMOVAL, 4"	HMA SURFACE REMOVAL, 2"	DESCRIPTION
STA	STA	(TON)	(TON)	(TON)	AREA (SY)	(SY)	
120+39	125+00		53.3			476.2	OUTSIDE SHOULDER
131+50	141+29		97.5			870.2	OUTSIDE SHOULDER
144+76	154+57		128.8			1,150.1	OUTSIDE SHOULDER
158+08	161+52		41.7			372.7	OUTSIDE SHOULDER
163+86	173+58		121.0			1,080.0	OUTSIDE SHOULDER
179+75	187+80		77.1			688.3	OUTSIDE SHOULDER
190+26	203+35		160.5			1,433.1	OUTSIDE SHOULDER
206+15	217+28		146.9			1,311.6	OUTSIDE SHOULDER
224+36	237+13		150.4			1,342.7	OUTSIDE SHOULDER
240+39	254+08		170.4			1,521.1	OUTSIDE SHOULDER
270+36	280+23		129.9			1,159.4	OUTSIDE SHOULDER
283+55	368+95		1,100.1			9,822.1	OUTSIDE SHOULDER
369+93	373+03		57.9			516.7	OUTSIDE SHOULDER
374+56	380+56		41.1			366.7	OUTSIDE SHOULDER
381+27	383+71		53.1			474.4	OUTSIDE SHOULDER
384+60	436+25		672.0			6,000.0	OUTSIDE SHOULDER
120+39	141+25		207.7			1,854.2	INSIDE SHOULDER
144+74	160+00		132.9			1,186.9	INSIDE SHOULDER
162+65	173+59		136.7			1,220.4	INSIDE SHOULDER
179+75	189+77		31.2			278.3	INSIDE SHOULDER
190+26	204+10		139.3			1,243.5	INSIDE SHOULDER
206+68	365+00		1,227.7			10,961.2	INSIDE SHOULDER
GORE AREA			472.5			4,218.8	
118+00.0	173+59.0	2,659.7				19,701.3	MAINLINE
179+73.3	187+79.7	290.3				2,150.4	MAINLINE
190+26.4	204+09.7	498.0				3,688.7	MAINLINE
206+67.5	433+60.0	9,404.1				69,660.0	MAINLINE
TAPERED LANES		548.5				4,063.3	MAINLINE
111TH ST RAMPS			354.3	455.6	3,615.7		RAMP AREA
115th ST RAMPS			390.1	501.5	3,980.2		RAMP AREA
130th ST RAMPS			259.2	333.3	2,645.2		RAMP AREA
DOTY AVE RAMPS			75.3	96.8	768.3		RAMP AREA
AREA BET. 111TH & 115TH ST. RAMPS			876.5	1,126.9	8,943.4		
DEDUCTIONS FOR BUTT JOINTS				(82.9)			
SUBTOTAL		13,400.6	7,504.8	2,431.1	19,952.8	148,812.3	
ROUNDED SUBTOTAL		13,401	7,505	2,432	19,953	148,813	
TOTAL		26,731	14,862	4,522	37,113	298,219	

FILE NAME =
D:\60C08-015-SCHEDULE.dgn

USER NAME = dvoznarski

DESIGNED -

DRAWN - DMW

CHECKED -

DATE - 2/6/2009

REVISED -

REVISED -

REVISED -

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**BISHOP FORD EXPRESSWAY (I-94)
SCHEDULES OF QUANTITIES**

SCALE: N/A

SHEET NO. 4 OF 9 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	0312-708W, ETC. & 1315RS-4	COOK	167	15
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 60C08	