

**CONTRACT 60C08
STONY ISLAND RESURFACING SCHEDULE**

EASTBOUND

LOCATION		HMA SURFACE COURSE, MIX "D", N70	HMA BINDER COURSE, IL-19, N70	POLYMERIZED HMA SURFACE COURSE, MIX "F", N90	POLYMERIZED HMA BINDER COURSE, IL-19, N90	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75 N50	HMA SURFACE REMOVAL, 1 1/2"	HMA SURFACE REMOVAL, 4"	DESCRIPTION
STA	STA	(SY)	(TON)			(TON)	(SY)	(SY)	
15+00	49+89	516.9	664.6				5,274.7		RAMP A SHOULDERS
10+00	43+39	423.1	544.0				4,317.5		RAMP D SHOULDERS
10+39	23+94	45.2	58.1				460.8		RAMP E SHOULDERS
15+73	23+06	87.9	113.0				896.9		RAMP F SHOULDERS
17+03	22+07	52.0	66.8				530.2		RAMP G SHOULDERS
23+06	30+00	70.2	90.3				716.3		RAMP F SHOULDERS
30+00	35+17	172.2	221.3				1,756.7		SB STONY ISLAND SHOULDERS
GORE AREA		227.9	293.0				2,325.6		
15+00	49+89			773.9		331.7			RAMP A PAVEMENT
10+00	43+39			669.2		286.8			RAMP D PAVEMENT
10+39	14+69			156.3		67.0			RAMP E PAVEMENT
15+73	23+06			111.7		47.9			RAMP F PAVEMENT
17+03	22+07			116.3		49.8			RAMP G PAVEMENT
23+06	30+00			177.6		76.1			RAMP F PAVEMENT
30+00	35+17			317.9		136.2			SB STONY ISLAND RAMP PAVEMENT
202+43	220+07			265.2	341.0			2,706.5	STONY ISLAND ENT TERMINAL RAMP PAVEMENT
146+05	149+23			55.7	71.6			568.0	STONY ISLAND EXT TERMINAL RAMP PAVEMENT
202+43	220+07	127.1	163.4					1,296.6	STONY ISLAND ENT TERMINAL RAMP SHOULDER
146+05	149+23	25.8	33.2					263.3	STONY ISLAND EXT TERMINAL RAMP RT & LT SHOULDER
DEDUCTIONS FOR BUTT JOINTS			(87.6)						
SUBTOTAL		1,748.2	2,160.1	2,643.7	412.6	995.5	16,278.7	4,834.4	
ROUNDED SUBTOTAL		1,749	2,161	2,644	413	996	16,279	4,835	

**CONTRACT 60C08
STONY ISLAND RESURFACING SCHEDULE**

WESTBOUND

LOCATION		HMA SURFACE COURSE, MIX "D", N70	HMA BINDER COURSE, IL-19, N70	POLYMERIZED HMA SURFACE COURSE, MIX "F", N90	POLYMERIZED HMA BINDER COURSE, IL-19, N90	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75 N50	HMA SURFACE REMOVAL, 1 1/2"	HMA SURFACE REMOVAL, 4"	DESCRIPTION
STA	STA	(SY)	(TON)	(TON)	(TON)	(TON)	(SY)	(SY)	
23+56	89+80	737.3	948.0				7,523.8		RAMP B SHOULDERS
10+87	12+25	35.9	46.1				366.0		RAMP J SHOULDERS
13+63	15+00	27.4	35.2				279.4		RAMP I SHOULDERS
13+48	32+74	265.3	341.1				2,707.2		RAMP H SHOULDERS
14+73	37+60	403.8	519.1				4,120.0		NB STONY ISLAND SHOULDERS
GORE AREA		172.7	222.1				1,762.4		
23+56	89+80			1,001.4		429.2			RAMP B PAVEMENT
10+00	11+65			43.1		18.5			RAMP C PAVEMENT
10+43	15+52			150.3		64.4			RAMP J PAVEMENT
12+10	15+49			69.9		30.0			RAMP I PAVEMENT
13+48	33+53			355.6		152.4			RAMP H PAVEMENT
14+73	35+03			622.6		266.8			NB STONY ISLAND RAMP PAVEMENT
TAPERED LANES				54.7		23.4			RAMP PAVEMENT
154+58	157+77			59.5	76.5			607.0	STONY ISLAND ENT TERMINAL RAMP PAVEMENT
216+47	220+99			155.6	200.1			1,588.0	STONY ISLAND EXT TERMINAL RAMP PAVEMENT
154+58	157+77	46.9	60.3					478.3	STONY ISLAND ENT TERMINAL RAMP SHOULDER
216+47	220+99	73.9	95.1					754.5	STONY ISLAND EXT TERMINAL RAMP RT & LT SHOULDER
DEDUCTIONS FOR BUTT JOINTS			(70.56)						
SUBTOTAL		1,763.2	2,196.4	2,512.7	276.6	984.7	16,758.8	3,427.7	
ROUNDED SUBTOTAL		1,764.0	2,197.0	2,513.0	277.0	985.0	16,759.0	3,428.0	
TOTAL SCHEDULE		3,513	4,358	5,157	690	1,981	33,038	8,263	

**CONTRACT 60C08
RESURFACING SUMMARY**

SCHEDULE	POLYMERIZED HMA SURFACE COURSE, SMA, N80 (TONS)	POLYMERIZED HMA SURFACE COURSE, MIX "F", N90 (TONS)	POLYMERIZED HMA BINDER COURSE, IL-19, N90 (TONS)	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75 (TONS)	HMA SURFACE COURSE MIX "D" N70 (TONS)	HMA BINDER COURSE, IL-19, N70 (TONS)	HMA SURFACE REMOVAL 1-1/2" (SY)	HMA SURFACE REMOVAL 2" (SY)	HMA SURFACE REMOVAL 4" (SY)
EASTBOUND MAINLINE (SHEET 3 OF 9)	13,330				7,357	2,090		149,406	17,160
WESTBOUND MAINLINE (SHEET 4 OF 9)	13,401				7,505	2,432		148,813	19,953
STONY ISLAND (SHEET 5 OF 9)		5,157	690	1,981	3,513	4,358	33,038		8,263
TOTAL	26,731	5,157	690	1,981	18,375	8,880	33,038	298,219	45,376