CONTRACT 60C08
SIGN SCHEDULE (CONTINUED)

				EXISTING		PROPOSED		REMOVE SIGN	REMOVE SIGN	SIGN PANEL	WOOD SIGN
				PANEL DIMENSIONS		PANEL DIMENSIONS		PANEL - TYPE 2	PANEL - TYPE 3	TYPE 3	SUPPORT
		STATION	LEGEND/DESCRIPTION	WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)	SQ FT	SQ FT	SQ FT	FOOT
WB-TR-45	1S016I094L068.9-000	388+19	115TH ST - 111TH ST - 2 MILES	12.0	8.0	12.0	10.0		96.0	120.0	
WB-TR-46	1S016I094L068.9-000	388+19	WEST 130TH ST - 1/4 MILE	12.0	9.0	11.0	9.5		108.0	104.5	
WB-TR-47	1S016I094L068.9-000	388+19	EAST 130 ST	12.5	8.0	13.5	8.0		100.0	108.0	
WB-BS-49	-	399+52	EAST 130 ST - 1/4 MILE	12.5	8.0	11.0	9.5		100.0	104.5	
WB-BS-50	-	404+92	ILLINOIS INT'L PORT EXITS	15.5	8.5	17.0	9.0		131.8	153.0	
WB-BS-51	-	416+67	130TH ST - 3/4 MILE	12.5	8.0	12.0	7.5		100.0	90.0	
WB-CL-57	1C016I094L069.9-000	442+14	130TH ST - 1 MILE	13.5	9.0	12.0	8.0		121.5	96.0	
WB-BR-77	UNKNOWN	114+00	I-57 SOUTH - MEMPHIS - EXIT ONLY	16.5	10.0	13.5	12.5		165.0	168.8	
WB-BR-78	UNKNOWN	114+00	I-94 WEST- RYAN EXPY-CHICAGO LOOP	12.0	10.0	16.5	10.0		120.0	165.0	
			WESTBOUND SUBTOTAL					105.0	3,105.5	3,578.8	216.0
			WESTBOUND ROUNDED SUBTOTAL					105	3,106	3,579	216

				EXISTING		PROPOSED		REMOVE SIGN	REMOVE SIGN	SIGN PANEL	WOOD SIGN
				PANEL DIMENSIONS		PANEL DIMENSIONS		PANEL - TYPE 2	PANEL - TYPE 3	TYPE 3	SUPPORT
SIGN NO.	STR. NO.	LOCATION	LEGEND/DESCRIPTION	WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)	SQ FT	SQ FT	SQ FT	FOOT
SI-TR-65	1S016I094L000.0-000	STONY IS	NORTH STONY ISLAND AVE	21.0	8.0	20.0	8.0		168.0	160.0	
SI-TR-66	1S016I094L000.0-000	STONY IS	103RD ST	11.0	6.0	10.0	5.5		66.0	55.0	
SI-TR-67	1S016I094R000.0-001	RAMP D	NORTH STONY ISLAND AVE - TO 95TH ST	21.0	10.0	20.0	10.0		210.0	200.0	
SI-TR-68	1S016I094R000.0-001	RAMP D	103RD ST	11.0	6.0	10.0	5.5		66.0	55.0	
SI-TR-69	1S016I094L000.0-001	RAMP B/J	NORTH STONY ISLAND AVE	17.0	11.0	15.5	11.0		187.0	170.5	
SI-TR-70	1S016I094L000.0-001	RAMP B/J	I-94 WEST - CHICAGO LOOP	20.5	8.0	18.5	7.5		164.0	138.8	
SI-TR-71	1S016I094R000.0-002	STONY IS	I-94 EAST - INDIANA	17.0	9.0	16.0	9.0		153.0	144.0	
SI-TR-72	1S016I094R000.0-002	STONY IS	103RD ST	11.0	6.0	10.0	5.5		66.0	55.0	
SI-TR-73	1S016I094R000.0-000	RAMP A	NORTH STONY ISLAND AVE - TO 95TH ST - KEEP LEFT	21.0	10.0	20.0	10.0		210.0	200.0	
SI-TR-74	1S016I094R000.0-000	RAMP A	103RD ST - RIGHT 1/2 MILE	12.0	6.0	14.0	5.5		72.0	77.0	
SI-BS-76	-	STONY IS	103RD ST - RIGHT 1/4 MILE	12.0	6.0	14.0	5.5		72.0	77.0	
			STONY ISLAND SUBTOTAL						1,434.0	1,332.3	
			STONY ISLAND ROUNDED SUBTOTAL						1,434	1,333	
			SCHEDULE TOTAL					228	7,665	8,706	504

CONTRACT 60C08
HOT MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)

EASTBOUND MAINLINE

STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	AREA (SY)
196+62	OUTSIDE SHOULDER	25	3	8.4
201+64	OUTSIDE SHOULDER	50	3	16.7
222+25	OUTSIDE SHOULDER	50	3	16.7
225+73	OUTSIDE SHOULDER	50	3	16.7
232+02	OUTSIDE SHOULDER	50	3	16.7
247+23	OUTSIDE SHOULDER	50	5	27.8
249+09	OUTSIDE SHOULDER	25	5	13.9
285+41	OUTSIDE SHOULDER	50	3	16.7
286+30	OUTSIDE SHOULDER	50	3	16.7
299+93	OUTSIDE SHOULDER	50	3	16.7
325+81	OUTSIDE SHOULDER	20	3	6.7
349+90	OUTSIDE SHOULDER	300	3	100.0
386+89	OUTSIDE SHOULDER	10	8	8.9
	SUBTOTAL EASTBOUND MAINLINE			282.6
	ROUNDED SUBTOAL EASTBOUND			283

WESTBOUND MAINLINE

STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	AREA (SY)
203+85	OUTSIDE SHOULDER	75	6	50.0
232+99	OUTSIDE SHOULDER	75	3	25.0
253+85	OUTSIDE SHOULDER	40	4	17.8
285+73	OUTSIDE SHOULDER	50	3	16.7
308+15	OUTSIDE SHOULDER	50	10	55.6
385+81	OUTSIDE SHOULDER	50	6	33.4
387+34	OUTSIDE SHOULDER	50	6	33.4
392+24	OUTSIDE SHOULDER	300	6	200.0
407+17	OUTSIDE SHOULDER	150	6	100.0
	SUBTOTAL WESTBOUND MAINLINE			531.9

EASTBOUND STONY ISLAND FEEDER RAMPS

RAMP	NUMBER	LOCATION	LENGTH (FT)	AVG. WIDTH (FT)	AREA (SY)
A	EB1	EXIT TERMINAL	25	3	8.3
A	EB2	RT SHOULDER	10	15	16.7
E, D	EB3	GORE BETWEEN RAMPS E & D	155	6.2	106.8
D	EB4	RT SHOULDER	355	8	315.6
		SUBTOTAL EASTBOUND STONY ISLAND FEEDER RAMPS			447.3
		ROUNDED SUBTOAL EASTBOUND STONY ISLAND FEEDER RAMPS			448

WESTBOUND STONY ISLAND FEEDER RAMPS

RAMP	NUMBER	LOCATION	LENGTH (FT)	AVG. WIDTH (FT)	AREA (SY)
B, J	WB1	GORE BETWEEN RAMPS B & J	163.8	10.7	194.7
H	WB2	RT SHOULDER	150	9	150.0
NB STONY ISLAND AVE	WB3	RT SHOULDER	150	10	166.7
STONY ISLAND EXIT RAMP	WB4	EXIT TERMINAL	12	7	9.3
STONY ISLAND EXIT RAMP	WB5	EXIT TERMINAL	25	6	16.7
		SUBTOAL WESTBOUND STONY ISLAND FEEDER RAMPS			520.7
		ROUNDED SUBTOAL WESTBOUND STONY ISLAND FEEDER RAMPS			521

TOTAL HOT MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)	1,784