



LEGEND

- (A)** PROPOSED MAINLINE RESURFACING

 - HOT - MIX ASPHALT SURFACE REMOVAL, 2"
 - POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80, 2"
- (B)** PROPOSED MAINLINE SHOULDER RESURFACING

 - HOT - MIX ASPHALT SURFACE REMOVAL, 2"
 - HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N70, 2"
- (C)** PROPOSED STONY ISLAND ENTRANCE AND EXIT TERMINALS RESURFACING.

 - HOT - MIX ASPHALT SURFACE REMOVAL, 4"
 - POLYMERIZED HOT - MIX ASPHALT BINDER COURSE, IL-19.0, N90, 2 - 1/4"
 - POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "F", N90, 1-3/4"
- (D)** PROPOSED STONY ISLAND FEEDER RAMP SHOULDER RESURFACING

 - HOT - MIX ASPHALT SURFACE REMOVAL, 1-1/2"
 - HOT - MIX ASPHALT BINDER COURSE, IL -19.0, N70, 2-1/4"
 - HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N70, 1-3/4"
- (E)** PROPOSED RAMP AND RAMP SHOULDER RESURFACING.

 - HOT - MIX ASPHALT SURFACE REMOVAL, 4"
 - HOT - MIX ASPHALT BINDER COURSE, IL-19.0, N70, 2-1/4"
 - HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N70, 1-3/4"
- (F)** PROPOSED STONY ISLAND ENTRANCE AND EXIT TERMINALS SHOULDER RESURFACING.

 - HOT - MIX ASPHALT SURFACE REMOVAL, 4"
 - HOT - MIX ASPHALT BINDER COURSE, IL -19.0, N70, 2-1/4"
 - HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N70, 1-3/4"
- (G)** PROPOSED STONY ISLAND FEEDER RAMP RESURFACING

 - POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL - 4.75, N50, 3/4"
 - AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A,
 - POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "F", N90, 1-3/4"
- HMA PATCH *** PROPOSED HOT MIX ASPHALT PAVEMENT PATCH. SEE SCHEDULE OF QUANTITIES
- PCC PATCH *** PROPOSED PORTLAND CEMENT CONCRETE PAVEMENT PATCH. SEE SCHEDULE OF QUANTITIES

FILE NAME = 0169088-839-PLAN.1.dgn	USER NAME = dvoznisark1	DESIGNED - DRAWN - DMW	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BISHOP FORD EXPRESSWAY (I-94) RESURFACING PLAN			F.A.I. RTE. 94	SECTION K0312-708W, ETC. & 1315RS-4	COUNTY COOK	TOTAL SHEETS 167	SHEET NO. 39
PLOT SCALE = 1/8" = 1' / IN. PLOT DATE = 2/6/2009					DATE = 2/6/2009	SCALE: 1" = 50'	SHEET NO. 1 OF 21 SHEETS	STA. 118+00 TO STA. 140+00	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT		CONTRACT NO. 60C08	