



SCHEDULE OF QUANTITIES

2814	2977	11.71	FT.	ELECTRICAL CABLE IN CONDUIT, NO. 6, 2/C
1188	454	11.71	FT.	ELECTRICAL CABLE IN CONDUIT, NO. 14, 1/C
2727	2590	11.71	FT.	ELECTRICAL CABLE IN CONDUIT, NO. 19, 6/C
		1.10	FT.	ELECTRICAL CABLE IN CONDUIT, NO. 13, 12/C
		1.10	FT.	G.S. CONDUIT IN TRENCH, 1-1/2"
289	400	11.71	FT.	G.S. CONDUIT IN TRENCH, 2"
		1.10	FT.	G.S. CONDUIT, PUSHED, 2"
287	326	11.71	FT.	G.S. CONDUIT ATTACHED TO STRUCTURE, 1-1/2"
		1.10	FT.	G.S. CONDUIT ATTACHED TO STRUCTURE, 2"
		1.10	FT.	INSTALL TELEPHONE DUCT
841	877	11.71	FT.	INSTALL POLYETHYLENE DUCT, 1-1/2"
1982	1932	11.71	FT.	INSTALL POLYETHYLENE DUCT, 2"
		1	EACH	EDCRETE FOUNDATION, TYPE 4
		3	EACH	CONCRETE FOUNDATION, TYPE D
		1	EACH	HEAVY DUTY HANDHOLE
		1	EACH	H HOLE
2531	2448	11.71	FT.	TRENCH AND BACKFILL
		1	EACH	BITUMINOUS CONCRETE SURFACE REMOVAL AND REPLACEMENT
		1	EACH	SERVICE INSTALLATION, TYPE C
		1	EACH	CABINET HOUSING EQUIPMENT, PEDESTAL MOUNTED, E.S.P. 1
		1	EACH	CABINET HOUSING EQUIPMENT, PEDESTAL MOUNTED, E.S.P. 2
		1	EACH	CABINET HOUSING EQUIPMENT, POLE MOUNTED, E.S.P. 1
		1	EACH	CABINET HOUSING EQUIPMENT, POLE MOUNTED, E.S.P. 2
		1	EACH	CABINET HOUSING EQUIPMENT, ATTACHED TO STRUCTURE, E.S.P. 1
		1	EACH	CABINET HOUSING EQUIPMENT, ATTACHED TO STRUCTURE, E.S.P. 2
417	308	11.71	FT.	INDUCTION LOOP
		1	EACH	INDUCTION LOOP DETECTOR POWER SUPPLY
		1	EACH	INDUCTION LOOP DETECTOR SENSOR UNIT
		1	EACH	TONE EQUIPMENT 3 FREQUENCY TRANSMITTER
		1	EACH	TONE EQUIPMENT 3 FREQUENCY MINIATURE TRANSMITTER
		1	EACH	TONE EQUIPMENT 3 FREQUENCY RECEIVER
		1	EACH	TONE EQUIPMENT POWER SUPPLY
		1	EACH	TONE EQUIPMENT MOUNTING FRAME
		1	EACH	INDUCTION LOOP DETECTOR POWER SUPPLY
		1	EACH	INDUCTION LOOP DETECTOR SENSOR UNIT

FOR INFORMATION ONLY

(0314-721-1 & E1) & (2426-721-1 & E1)

STATE OF ILLINOIS
DIVISION OF HIGHWAYS
CHICAGO AREA EXPRESSWAY SURVEILLANCE PROJECT

III TH STREET INSTALLATION
(SHEET 1 OF 2)

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	0312-708R, ETC. & 1315RS-4	COOK	167	142
DRAWN BY	SCALE	DATE	ENTERED BY	APPROVED BY
PSC	NONE	4/2/72	RCS	JMG