

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
607	13 B-I-1	WILL	16	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 60C89

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, LIST OF STATE STANDARDS AND GENERAL NOTES U.S. RTE. 30
3	SUMMARY OF QUANTITIES U.S. RTE. 30
4	CONSTRUCTION STAGING NOTES, TEMPORARY PAVEMENT MARKING SCHEDULE & PERMANENT PAVEMENT MARKING SCHEDULE U.S. RTE. 30
5	CONSTRUCTION STAGING TYPICAL SECTIONS U.S. RTE. 30
6	SUGGESTED TRAFFIC CONTROL AND PROTECTION STAGES I, II AND III U.S. RTE. 30

S.N. 099-0105

7	GENERAL PLAN & ELEVATION
8	DECK CROSS SECTION
9	DECK CONCRETE PATCHING
10	EXPANSION JOINT DETAILS
11	PREFORMED JOINT STRIP SEAL
12	BAR SPLICER ASSEMBLY DETAILS
13	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS
14	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)
15	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
16	ARTERIAL ROAD INFORMATION SIGNING

LIST OF STATE STANDARDS

STANDARD NO.	DESCRIPTION
701201-03	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH
701301-03	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701901-01	TRAFFIC CONTROL DEVICES

GENERAL NOTES:

1. THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM I.D.O.T. FIELD MAINTENANCE ENGINEERS.
2. THE RESIDENT ENGINEER MUST CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847)705-4470 AT LEAST 72 HOURS PRIOR TO INSTALLATION OF THE TEMPORARY CONTROL DEVICES.
3. THE RESIDENT ENGINEER SHALL CONTACT CORA MATHIS THE AREA TRAFFIC FIELD ENGINEER AT (815)485-6475 TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
4. ALL PAVEMENT MARKINGS AND RAISED REFLECTORS AFFECTED BY THE BRIDGE REPAIRS SHALL BE REPLACED. NOMINAL QUANTITIES HAVE BEEN INCLUDED IN THE CONTRACT FOR THIS WORK.
5. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
6. DO NOT SCALE THESE PLANS FOR CONSTRUCTION PURPOSES.
7. WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR MUST EXERCISE THE UTMOST PRECAUTIONS IN PREVENTIVE ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND TO THE ADJOINING RESIDENTIAL AREAS.
8. PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE BID FOR THE WORK.
9. ALL RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE) SHALL BE LOW PROFILE.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS,
LIST OF STATE STANDARDS
AND GENERAL NOTES
U.S. RTE. 30

SCALE: NONE
DATE: JANUARY 08, 2009

DRAWN BY: D.L./F.M.
CHECKED BY: B.N.S./S.J.P.

CHRISTIAN-ROGE & ASSOC., INC.
CHICAGO ILLINOIS