# TEMPORARY PAVEMENT MARKING SCHEDULE

UNIT	STAGE I	STAGE II	STAGE III	TOTAL QUANTITIES
FOOT	2,236	2,236	2,236	6,708
EACH	12	_	12	24
SQ. FT.	1,118	nun.		1,118
	FOOT	F00T 2,236  EACH 12	F00T 2,236 2,236  EACH 12 -	FOOT 2,236 2,236 2,236 EACH 12 - 12

## PERMANENT PAVEMENT MARKING SCHEDULE

	ITEM UNIT LOCATION		QUANTITIES	TOTAL QUANTITIES	
			STA. 86+92.00 TO STA. 98+10.00		
	POLYUREA, TYPE I -LINE 4" White edge line Double yellow lines	F00T F00T	STA. 91+57.00 TO STA. 93+47.00 STA. 91+57.00 TO STA. 93+46.00	2 LINES AT 190 FT. 2 LINES AT 190 FT.	380 380
Ī	THERMOPLASTIC -LINE 4"				
	WHITE EDGE LINE	FOOT	STA. 86+92 TO STA. 91+57 STA. 93+47 TO STA. 98+10	2 LINES AT 928 FT.	1856
	DOUBLE YELLOW LINES	FOOT	STA. 86+92 TO STA. 91+57 STA. 93+47 TO STA. 98+10	2 LINES AT 928 FT.	1856
<del>-</del>	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	STA. 91+57.00 TO STA. 93+46.00	10	10

straised reflective pavement marker (bridge) ARE 2-2 WAY AMBER, SPACED AT 40' C-C

_	F.A.P. RTE.	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
	607	13 B-I-1		WILL	16	4
	STA. TO STA.					
FED. ROAD DIST. NO.		I	ILLINOIS	FED.	AID PROJECT	

CONTRACT NO. 60C89

## **CONSTRUCTION STAGING NOTES:**

## STAGE I

WORK ACTIVITIES SHALL CONSIST OF REMOVING THE EXISTING OVERLAY, PATCHING, RECONSTRUCT ABUTMENT JOINTS AND OVERLAYING THE SOUTH RIGHT 1/3 OF THE BRIDGE.

TRAFFIC CONTROL FOR THIS STAGE SHALL CONSIST OF THE SHIFTING OF BOTH LANES OF TRAFFIC ONTO THE WESTBOUND LANE AND SHOULDER ACROSS THE BRIDGE AS SHOWN ON THE TRAFFIC CONTROL PLANS. THE ADJACENT SIDEROADS SHALL BE SIGNED IN ACCORDANCE WITH DETAIL TC-10.

### STAGE II

WORK ACTIVITIES SHALL CONSIST OF REMOVING THE EXISTING OVERLAY, PATCHING, RECONSTRUCT ABUTMENT JOINTS AND OVERLAYING THE CENTER PORTION OF THE BRIDGE.

TRAFFIC CONTROL- WESTBOUND TRAFFIC SHALL REMAIN IN THE STAGE I CONFIGURATION. EASTBOUND TRAFFIC SHALL BE SHIFTED ONTO THE NEWLY OVERLAYED PART OF THE BRIDGE.

WORK ACTIVITIES SHALL CONSIST OF REMOVING THE EXISTING OVERLAY, PATCHING, RECONSTRUCT ABUTMENT JOINTS AND OVERLAYING THE REMAINING PORTION OF THE BRIDGE. THE FINAL PAVEMENT MARKINGS AND RAISED PAVEMENT MARKERS WILL BE PLACED AT THE END OF STAGE III.

TRAFFIC CONTROL - WESTBOUND TRAFFIC SHALL BE MOVED ONTO THE NEWLY OVERLAYED CENTER PORTION OF THE BRIDGE. A TEMPORARY DOUBLE YELLOW CENTERLINE AND TEMPORARY RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED TO SEPARATE THE TWO LANES OF TRAFFIC.

## OTHER TRAFFIC CONTROL NOTES:

- 1. ALL TEMP. PAVEMENT MARKINGS SHALL BE WET REFLECTIVE TEMP. MRK TAPE , TYPE III 4".
- 2. ALL CONFLICTING PAVEMENT MARKINGS SHALL BE REMOVED DURING STAGE I.
- 3. THE ENGINEER SHALL BE INFORMED 48 HOURS IN ADVANCE OF ANY CHANGE IN CONSTRUCTION STAGING.

REVISIONS

ILLINOIS DEPARTMENT OF TRANSPORTATION

CONSTRUCTION STAGING NOTES. TEMPORARY PAVEMENT MARKING SCHEDULE & PERMANENT PAVEMENT MARKING SCHEDULE U.S. RTE. 30

SCALE: NONE DATE: JANUARY 08, 2009

DRAWN BY: D.L./F.M. CHECKED BY: B.N.S./S.J.P.

CHRISTIAN-ROGE & ASSOC., INC. CHICAGO