

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	URBAN 100% P20 TOTAL	EB	WB	SFTY-3J	SN 016-0162	SN 016-0163
				ROADWAY	ROADWAY		BRIDGES	BRIDGES
				1000 - 2A			X231-2A	X031-2A
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	95	45	50			
25000210	SEEDING, CLASS 2 A	ACRE	2.5	1.25	1.25			
28000400	PERIMETER EROSION BARRIER	FOOT	9,617	4,640	4,977			
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	3,710	3,434	276			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	58	29	29			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	31	15	16			
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	590	293	297			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	675	275	400			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	771	397	374			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8,883	4,396	4,487			
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	840	420	420			
44000100	PAVEMENT REMOVAL	SQ YD	655	333	322			
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	49,908	23,680	26,228			
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	30,289	15,774	14,515			
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	6,111	3,146	2,965			
44000166	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/4"	SQ YD	100,018	49,770	50,248			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	381	161	220			
44001980	CONCRETE BARRIER REMOVAL	FOOT	62	62				
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	15		15			
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SQ YD	1,995	818	1,177			
44004250	PAVED SHOULDER REMOVAL	SQ YD	15,938	10,058	5,880			
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	10		10			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	872	327	545			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	321	179	142			
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	500	182	318			
44213200	SAW CUTS	FOOT	60		60			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	114,238	57,092	57,146			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	269	77	192			
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	2,358	676	1,682			
48203053	HOT-MIX ASPHALT SHOULDERS, 14"	SQ YD	8,715	4,821	3,894			
50102400	CONCRETE REMOVAL	CU YD	80.0				40.0	40.0

* SPECIALTY ITEM

FILE NAME = D:\60021-003-500.dgn

USER NAME = dwozniarski

DESIGNED -

REVISED -

DRAWN - DMW

REVISED -

PLOT SCALE = N/A

CHECKED -

REVISED -

PLOT DATE = 2/7/2009

DATE - 2/7/2009

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BISHOP FORD EXPRESSWAY (I-94)
SUMMARY OF QUANTITIES

SCALE: N/A

SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.I.
RTE.
94

SECTION
(0405,ETC,42-7&0707)RS-II

COUNTY
COOK

TOTAL SHEETS
133

SHEET NO.
3

CONTRACT NO. 60D21

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT