

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	URBAN 100% P&D TOTAL	1000 - 2A		SFTY-3J	SN 016-0162 BRIDGES X231 - 2A	SN 016-0163 BRIDGES X031 - 2A
				EB ROADWAY	WB ROADWAY			
X0325349	TEMPORARY CONCRETE BARRIER (TO REMAIN PERMANENTLY)	FOOT	282			282		
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.5	0.5			
X0325739	HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)	SQ YD	224	190	34			
X0325765	ANTHCING SURFACE OVERLAY	SQ YD	7,210				3,860	3,350
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	177,650	92,398	85,252			
X0325864	BRIDGE APPROACH PAVEMENT REMOVAL	SQ YD	1,156	565	591			
X0325876	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	27,843	14,379	13,464			
X0326107	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	FOOT	45,557	23,307	22,250			
50600300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1					1
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	11,816	5,880	5,936			
X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	11,774	5,859	5,915			
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5,898	2,974	2,924			
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	72				36	36
X6050700	REMOVE INLET BOX	EACH	6	3	3			
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.5	0.5			
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	250	125	125			
* X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 4/C, TWISTED, SHIELDED	FOOT	2,018	1,165	853			
* X8850102	INDUCTION LOOP	FOOT	710	355	355			
XX003988	TEMPORARY CONCRETE BARRIER REMOVAL	FOOT	682	682				
Z0010400	CLEANING BRIDGE SEATS	SQ FT	1,191				581	610
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5			
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	361				193	168
Z0017202	DOWEL BARS 1 1/2"	EACH	24		24			
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	201	110	91			
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	11	6	5			
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	12	6	6			
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1			
Z0076600	TRAINEES	hour	3500	3500				

* SPECIALTY ITEM

NP = Non-participating
 © Y080

FILE NAME = D:\62021-006-900.dgn

USER NAME = dwozniarski

DESIGNED -

REVISED -

DRAWN - DMW

REVISED -

CHECKED -

REVISED -

DATE - 2/7/2009

REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

BISHOP FORD EXPRESSWAY (I-94)
 SUMMARY OF QUANTITIES

SCALE: N/A

SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A.I.
 RTE.

SECTION

COUNTY

TOTAL SHEETS

SHEET NO.

94

(0405,ETC,42-7&0707)RS-11

COOK

133

6

CONTRACT NO. 60D21

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT