



**LEGEND**

- Ⓐ PROPOSED MAINLINE RESURFACING
  - HOT-MIX ASPHALT SURFACE REMOVAL, 4-1/4"
  - POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80, 1-3/4"
  - POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80, 1-3/4"
  - POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50, 3/4"
- Ⓑ PROPOSED MAINLINE SHOULDER RESURFACING
  - HOT MIX ASPHALT SURFACE COURSE, MIX "D", N70, 1-3/4"
  - HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 1-3/4"
- Ⓒ PROPOSED RAMP AND RAMP SHOULDER RESURFACING (SIBLEY BLVD ONLY)
  - HOT MIX ASPHALT SURFACE REMOVAL, 4"
  - HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 1-3/4"
  - HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70, 2-1/4"
- Ⓓ PROPOSED MAINLINE SHOULDER RECONSTRUCTION
  - HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 1-3/4"
  - HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70, 12-1/4"
- Ⓔ PROPOSED RAMP SHOULDER RECONSTRUCTION
  - HOT MIX ASPHALT SURFACE COURSE, MIX "D", N70, 1-3/4"
  - HOT MIX ASPHALT BINDER COURSE, IL-19.0, N70, 8-1/4"
- Ⓕ PROPOSED RAMP AND RAMP SHOULDER RESURFACING (US 6 ONLY)
  - HOT MIX ASPHALT SURFACE REMOVAL, 3"
  - HOT MIX ASPHALT SURFACE COURSE, MIX "D", N70, 2"
  - POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50, 1"
- HMA PATCH ■ PROPOSED HOT MIX ASPHALT PAVEMENT PATCH, SEE SCHEDULE OF QUANTITIES
- PCC PATCH ■ PROPOSED PORTLAND CEMENT CONCRETE PAVEMENT PATCH, SEE SCHEDULE OF QUANTITIES

NOTE: AREAS OF SHOULDER RECONSTRUCTION INCLUDES THE PAY ITEMS PAVED SHOULDER REMOVAL, EXCAVATION AND GRADING EXISTING SHOULDER, AND HOT MIX ASPHALT SHOULDER 10" FOR US 6 RAMPS.

NOTE: SEE SHEET 5 OF 9 FOR RESURFACING ON MAINLINE PAVEMENT

SEE SHEET 7 OF 9

SEE SHEET 9 OF 9

FILE NAME = 0160021-027-PLAN-8.dgn	USER NAME = dwozniarski	DESIGNED - DRAWN - DMW	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BISHOP FORD EXPRESSWAY (I-94) RESURFACING PLAN	F.A.I. RTE. 94	SECTION 10405.ETC.42-7&0707RS-11	COUNTY COOK	TOTAL SHEETS 133	SHEET NO. 27
PLOT SCALE = 1/8" = 1'-0"	PLOT DATE = 2/5/2009	CHECKED - DATE - 2/5/2009	SCALE: 1" = 50'			SHEET NO. 8 OF 9 SHEETS	STA. 605+00 TO STA. 607+28	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT CONTRACT NO. 60021		