

## INDEX OF SHEETS

- 1 COVER SHEET
  - 2 INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES, AND COMMITMENTS
  - 3 SUMMARY OF QUANTITIES
  - 4 ROADWAY PLAN
  - 5 MAINTENANCE OF TRAFFIC NOTES AND DESCRIPTION
  - 6 SUGGESTED STAGES OF CONSTRUCTION AND TRAFFIC CONTROL - STAGE 1
  - 7 SUGGESTED STAGES OF CONSTRUCTION AND TRAFFIC CONTROL - STAGE 2
  - 8 PAVEMENT MARKING PLAN
  - 9-11 TEMPORARY TRAFFIC SIGNAL PLANS
  - 12 TEMPORARY AERIAL CABLE INSTALLATION (BE-801)
  - 13-16 STANDARD TRAFFIC SIGNAL DESIGN DETAILS (TS-05)
  - 17-28 STRUCTURAL PLANS
  - 29 BUTT JOINT AND HMA TAPER DETAILS (BD400-05)
  - 30 TRAFFIC CONTROL DETAILS FOR FREEWAY, SINGLE & MULTI-LANE WEAVE, (TC-9)
  - 31 RAISED REFLECTIVE PAVEMENT MARKERS, SNOW PLOW RESISTANT, (TC-11)
  - 32 DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)
  - 33 TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES, PARTIAL RAMP CLOSURES (TC-17)
  - 34 ARTERIAL ROAD INFORMATION SIGN (TC-22)
- HIGHWAY STANDARDS

## LIST OF ILLINOIS DOT HIGHWAY STANDARDS

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
- 001001-02 AREAS OF REINFORCEMENT BARS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 631031-07 TRAFFIC BARRIER TERMINAL, TYPE 6
- 701311-03 LANE CLOSURE 2 LANE 2 WAY MOVING OPERATIONS DAY ONLY
- 701316-04 LANE CLOSURE, 2L, 2W, BRIDGE REPAIR FOR SPEEDS >= 45 MPH
- 701901-01 TRAFFIC CONTROL DEVICES
- 701400-03 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701401-05 LANE CLOSURE, FREEWAY/EXPRESSWAY

## GENERAL NOTES

1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
2. THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTENANCE BRIDGE INSPECTORS.
3. DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.
4. ALL DAMAGE TO EXISTING PAVEMENT MARKING OR RAISED REFLECTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTORS EXPENSE. NO ADDITIONAL COST TO THE DEPARTMENT.
5. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH THE UTILITY COMPANIES INCLUDING THE VILLAGE OF PEOTONE.
6. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
8. BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD (FOR FUTURE REFERENCES), ALL EXISTING PAVEMENT MARKING LINES AND RAISED REFLECTIVE PAVEMENT MARKERS IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL STRIPING SHALL BE AS DIRECTED BY THE ENGINEER.
9. THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK ALONG PEOTONE ROAD.
10. THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4151 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK ALONG I-57.
11. THE ENGINEER SHALL CONTACT CORA MATHIS TRAFFIC FIELD ENGINEER AT (815) 485-6475 A MINIMUM OF TWO WEEKS PRIOR TO PLACE OF PERMANENT PAVEMENT MARKINGS.
12. ALL PAVEMENT MARKINGS AND RAISED REFLECTORS AFFECTED BY THE BRIDGE REPAIRS AND MAINTENANCE OF TRAFFIC SHALL BE REPLACED. NOMINAL QUANTITIES HAVE BEEN INCLUDED IN THE PLANS.
13. THE "ADVANCE WARNING SIGN DETAIL FOR ARTERIAL TRAFFIC" LOCATED IN THE SPECIAL PROVISIONS FOR "TEMPORARY INFORMATION SIGNING FOR LANE CLOSURES" AND THE SPECIAL PROVISION FOR "PUBLIC CONVENIENCE IS/ARE APPLICABLE ONLY TO ARTERIAL ROADS AND SHALL NOT BE APPLIED TO EXPRESSWAYS/TOLLWAYS.
14. THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
15. DOUBLE LANE MARKERS ARE TO BE USED AS SHOWN ON THE DISTRICT ONE DETAIL "TYPICAL APPLICATIONS - RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" SHOWN ON THE PLANS.

## COMMITMENTS

NO COMMITMENTS FOR THIS PROJECT

PLOT DATE : 1/14/2009  
 PLOT SCALE : 1:8000 / IN.  
 USER NAME : Millennium Engineering  
 MODEL : #MODEL\$



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.705.0110 voice, 630.839.2566 fax  
 www.millenniaeng.com  
**MILLENNIA ENGINEERING**

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE - 1/14/2009	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**FAI 57A-57**  
**AT NORTH PEOTONE-**  
**JOILET RD**

**INDEX OF SHEETS, LIST OF IDOT**  
**HIGHWAY STANDARDS, GENERAL**  
**NOTES, AND COMMITMENTS**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	99-2HB-1-I-2	WILL	33	2
CONTRACT NO. 60D65				

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

P:\2007\ME07080\_VerVar\_Plan\Cadd\W01\Shets\Rdwy\02Index\_Peot.dgn