

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				099-0162 SFTY-2A QUANTITY	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	20.5	20.5	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	40.9	40.9	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	240	240	
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.8	4.8	
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	241.5	241.5	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	40	40	
50102400	CONCRETE REMOVAL	CU YD	11.6	11.6	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	12.7	12.7	
50300260	BRIDGE DECK GROOVING	SQ YD	884	884	
50300300	PROTECTIVE COAT	SQ YD	34	34	
50300530	FLOOR DRAIN EXTENSION	EACH	13	13	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1271	1271	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	12	12	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1450	1450	
50800515	BAR SPLICERS	EACH	20	20	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	80	80	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12	12	
52100520	ANCHOR BOLTS, 1"	EACH	24	24	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	229	229	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	70	70	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	3	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1199	1199	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1729	1729	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	16	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10	10	

* SPECIALTY ITEM

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				099-0162 SFTY-2A QUANTITY	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	286.2	286.2	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	26	26	
X0321468	PLUG EXISTING DECK DRAINS	EACH	1	1	
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	930	930	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	119	119	
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	3609	3609	
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	24	24	
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1	
X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	930	930	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	2	2	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	78	78	
Z0065700	SLOPE WALL REPAIR	SQ YD	15	15	

* SPECIALTY ITEM

1/13/2009 11:57:28 AM P:\11\Cadd\W01\Shs\RDwy\Peotone_S00_03.dgn
 MILLENNIA ENGINEERING



200 22ND Street, Suite 216, Lombard, IL 60148
 630.705.0110 voice, 630.839.2566 fax
 www.millenniaeng.com
MILLENNIA ENGINEERING

DESIGNED - TVN	REVISED -
DRAWN - TVN	REVISED -
CHECKED - RPD	REVISED -
DATE - 1/13/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAI 571-57
AT NORTH PEOTONE-
JOILET RD

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE. 57	SECTION 99-2HB-1-1-2	COUNTY WILL	TOTAL SHEETS 33	SHEET NO. 3
CONTRACT NO. 60D65				

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT
 P:\2007\ME07080_Vis_Ver_Phil\Cadd\W01\Shs\RDwy\Peotone_S00_03.dgn