

SUMMARY OF QUANTITIES			URBAN	100% FED
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
				IL. RTE. 102 BRIDGE SFTY-2A
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1
40600300	AGGREGATE (PRIME COAT)	TON	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	26	26
40600990	TEMPORARY RAMP	SQ YD	268	268
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	60	60
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	40	40
42001300	PROTECTIVE COAT	SQ YD	107	107
44000086	HOT-MIX ASPHALT SURFACE REMOVAL COMPLETE	SQ YD	107	107
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	474	474
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	6	6
50300260	BRIDGE DECK GROOVING	SQ YD	102	102
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,340	1,340
50800515	BAR SPLICERS	EACH	24	24
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,430	1,430
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	8
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2
78300100	PAVEMENT MARKING REMOVAL	SQ FT	184	184
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10

* SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN	100% FED
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
				IL. RTE. 102 BRIDGE SFTY-2A
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1
* 81800300	AERIAL CABLE, 3-1/2 NO. 2 WITH MESSENGER WIRE	FOOT	1,370	1,370
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	7	7
* 83057120	LIGHT POLE, WOOD, 25 FOOT, CLASS 4	EACH	1	1
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	7	7
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	7	7
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	3	3
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	6	6
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	108	108
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	1,440	1,440
* X0325867	COMBINATION POLE MOUNTED ELECTRIC SERVICE BOX	EACH	1	1
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	107	107
* X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1
* XX006937	GROUND ROD, 5/8" DIA. x 10 FT.	EACH	2	2
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
* X0326135	ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL	EACH	1	1

* SPECIALTY ITEM

FILE NAME = 60073 summary.dgn
PLOT DATE = 1/12/2009



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5278

DESIGNED - S.J.P.
DRAWN - A.C.S.
CHECKED - E.J.M.
DATE - JANUARY 12, 2009

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL. RTE. 102

F.A.P.
RTE.
631

SECTION
111 N-B-1

COUNTY
WILL

TOTAL SHEETS
20

SHEET NO.
3

CONTRACT NO. 60D73

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 741+60 TO STA. 743+20

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT