



**LEGEND:**

- TEMPORARY LIGHTING UNIT  
50 FT. MOUNTING HEIGHT, 15 FT. MAST ARM  
400 WATT, 120 VOLT LUMINAIRE WITH PHOTOCELL  
ON EACH LUMINAIRE
- AERIAL CABLE, 3-1/C NO. 4, ALUMINUM, WITH MESSENGER WIRE
- GROUND ROD, 5/8" DIAMETER X 10 FT.
- ELECTRIC SERVICE DISCONNECT, LIGHTING  
AND TRAFFIC SIGNAL
- EXISTING UTILITY POLE

**NOTES**

1. TEMPORARY LIGHTING SHALL BE INSTALLED AND OPERATIONAL BEFORE THE START OF CONSTRUCTION.
2. POLE SHALL BE SETBACK 18 FT. FROM THE EDGE OF THE TRAVELLED PAVEMENT, UNLESS OTHERWISE REQUIRED BY THE FIELD CONDITIONS.
3. TEMPORARY LIGHTING SHALL REMAIN OPERATIONAL FOR BOTH STAGE I AND STAGE II. STAGE I SHOWN.
4. ALL POLES SHOWN ON THIS PLAN SHALL BE INSTALLED BY THE LIGHTING CONTRACTOR.



FILE NAME = n:\proj\332\332\_26\design\lighting\332\_26-1.rpt.plt

**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
6507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60655  
Tel: 773.775.4005 Fax 773.775.4014

USER NAME = wlencaster	DESIGNED - JMV	REVISED -
PLOT SCALE = 5/16" = 1' IN.	DRAWN - MB	REVISED -
PLOT DATE = 1/13/2009	CHECKED - JMV	REVISED -
	DATE - 05/15/2008	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**FAP 332 / ILLINOIS ROUTE 1  
ILLINOIS ROUTE 1 OVER TRIM CREEK  
TEMPORARY LIGHTING PLAN**

SCALE: 1"=50'    SHEET NO. 1 OF 4 SHEETS    STA.    TO STA.

F.A.P. RTE. 332	SECTION 8 R-B-I-2	COUNTY WILL	TOTAL SHEETS 28	SHEET NO. 12
FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 60D81	