

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITY	CONSTRUCTION CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000-2A	BRIDGE Y007
20200100	EARTH EXCAVATION	CU YD	120	120	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	240	240	
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1	
25100630	EROSION CONTROL BLANKET	SQ YD	470	470	
31101600	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	350	350	
35501288	HOT-MIX ASPHALT BASE COURSE, 2 1/2"	SQ YD	220	220	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	95	95	
40600300	AGGREGATE (PRIME COAT)	TON	2	2	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	60	60	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	65	65	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	125	125	
42001300	PROTECTIVE COAT	SQ YD	182		182
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	650	650	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,010	1,010	
44003100	MEDIAN REMOVAL	SQ FT	3,120	3,120	
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	203		203
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	220	220	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3.3		3.3
50300260	BRIDGE DECK GROOVING	SQ YD	149		149
60260100	INLETS TO BE ADJUSTED	EACH	2	2	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	125	125	
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	990	990	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	63	63	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	420	420	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	1	3
67100100	MOBILIZATION	L SUM	1	0.2	0.8
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.2	0.8
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	90	18	72
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	8	

* SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITY	CONSTRUCTION CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000-2A	BRIDGE Y007
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,450	4,450	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	375	375	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	238	238	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	75	75	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13,100	13,100	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	380	380	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	65	65	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	30	30	
* 78100300	REPLACEMENT REFLECTOR	EACH	180	180	
* 78200450	MONODIRECTIONAL GUARDRAIL REFLECTORS	EACH	8	8	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	25	25	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4,800	4,800	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	30	30	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	2	
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	180	180	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	149		149
X0325239	TEMPORARY PAVEMENT 10"	SQ YD	160	160	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	8		8
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	12,000	12,000	
X0325837	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	410	410	
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	65	65	
X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	73	73	
Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SQ YD	1		1
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	414		414
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.2	0.8
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	7.3		7.3
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

FILE NAME = N:\PROJ\3329\3329_2\Design\ProposedPlan\3329_2-9-03-road.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = wjanoaster	DESIGNED - JCC	REVISED -
PLOT SCALE = 1:8000' / IN.	DRAWN - JCC	REVISED -
PLOT DATE = 1/13/2009	CHECKED - MJL	REVISED -
	DATE - 12/30/07	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAP 347 / ILLINOIS ROUTE 38 (ROOSEVELT ROAD)
OVER KRESS CREEK
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
347	2 Y-B-1	DU PAGE	34	3
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT			CONTRACT NO. 60D82	