

SUMMARY OF QUANTITIES			100% FED. URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000-2A	BRIDGE X081-2A
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	105	105	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	60	60	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	45	45	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	510	510	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	208		208
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	251	251	
50300260	BRIDGE DECK GROOVING	SQ YD	208		208
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	88	88	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	558	558	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	1	3
67100100	MOBILIZATION	L SUM	1	0.2	0.8
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.2	0.8
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	0.2	0.8
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	8	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,067	1,067	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	274	274	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	274	274	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,740	1,740	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	100	100	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	1	1	
* 78200450	MONODIRECTIONAL GUARD RAIL REFLECTORS	EACH	8	8	
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	25	25	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	

* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES			100% FED. URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000-2A	BRIDGE X081-2A
78300105	PAVEMENT MARKING REMOVAL	FOOT	2,025	2,025	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12	12	
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1	
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	7	7	
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	7	7	
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	7	7	
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26	
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	4	4	
X0323818	CLEANING AND PAINTING EXPOSED REBAR	SQ FT	450		450
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	29		29
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	3,057	3,057	
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	24	24	
X0326133	TEMPORARY WOOD POLE, 45 FT, CLASS 5	EACH	2	2	
* X0326135	ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL	EACH	1	1	
* B1800320	AERIAL CABLE, 3-1/C NO. 4, ALUMINUM, WITH MESSENGER WIRE	FOOT	1,350	1,350	
* X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
* XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	3	3	
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	208		208
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	208		208
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.2	0.8
Z0015595	DECK DRAIN EXTENSIONS	EACH	12		12
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1.1		1.1
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	5.1		5.1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1	

42101500 PROTECTIVE COAT 59 YD 208 208

FILE NAME = N:\PROJ\3329\3329\27\Design\ProposedPlan\3329_27-esq.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60658
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = wjancaster	DESIGNED - DMM	REVISED -
	DRAWN - DMM	REVISED -
PLOT SCALE = 1:20000 ' / IN.	CHECKED - MJL	REVISED -
PLOT DATE = 1/13/2009	DATE - 05/15/2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**FAP 852 /US ROUTE 52
US ROUTE 52 OVER JACKSON CREEK
SUMMARY OF QUANTITIES**

F.A.P. RTE. 852	SECTION 18 B-4-R-1	COUNTY WILL	TOTAL SHEETS 27	SHEET NO. 3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60D84	

Rev.