

SUMMARY OF QUANTITIES

URBAN
100% F&D.

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	QUANTITY X071-2A
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	46
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	120
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	348
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	889
50102400	CONCRETE REMOVAL	CU YD	21
50157300	PROTECTIVE SHIELD	SQ YD	105
50300255	CONCRETE SUPERSTRUCTURE	CU YD	21
50300260	BRIDGE DECK GROOVING	SQ YD	877
50300300	PROTECTIVE COAT	SQ YD	1,240
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6,780
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	16
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3,340
50800515	BAR SPLICERS	EACH	24
52000110	PREFORMED JOINT STRIP SEAL	FOOT	146
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	16
52100520	ANCHOR BOLTS, 1"	EACH	32
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	70
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1,134
70300510	PAVEMENT MARKING TAPE, TYPE III-LETTERS AND SYMBOLS	SQ FT	73
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	7,907
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	90
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,296
70400100	TEMPORARY CONCRETE BARRIER	FOOT	383
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	383
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8,542
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	180
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	664
* 78006110	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	688
* 78006150	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	46
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	199
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	16
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4,230
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	215
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2"	SQ YD	889
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH ≤ 5")	SQ FT	63
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	20
70101800	CHANGEABLE MESSAGE SIGN	CAL MO	6
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION, 1/2"	SQ YD	889
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	5
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	42
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = .USER.	DESIGNED - WS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILEL		DRAWN - AJR	REVISED -		352	56 B-1-2	LAKE	26	3			
	PLOT SCALE = 18.0000' / IN.	CHECKED - RJS	REVISED -		SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.			FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 60D91		
	PLOT DATE = 1/13/2009	DATE - 01/14/09	REVISED -		H:\Jobs\2006\20063028-44\CAD\Site\dgn\00\Summary of Quantities-44_V8.dgn 1/13/2009 2:43:33 PM							