

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1467	2008-024RS	COOK	21	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

D-91-469-08

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT		TOTAL QUANTITIES	1000 31st ST.	1000 GOLFVIEW ROAD					CODE NO		ITEM	UNIT	TOTAL QUANTITIES	1000 31st ST.	1000 GOLFVIEW ROAD		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11	6.2	4.8					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	206	106	100				
40600300	AGGREGATE (PRIME COAT)	TON	43	30.8	12.2					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	182	182	0				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4.1	2.3	1.8					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7859	4328	3531				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	0					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	533	533	0				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	342	222	120					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	390	390	0				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	126	71	55					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	136	71	65				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1193	664	529					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	227	160	67				
42001300	PROTECTIVE COAT	SO YD	45	45	0					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	182	182	0				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	13797	7679	6118					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	638	305	333				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200	0					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	102.8	51.4	51.4				
44002213	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/4"	SO YD	690	390	300					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	597	332	265				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1	0					* Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2	2	0				
60404940	FRAMES AND GRATES, TYPE 23	EACH	2	2	0					X4420006	CLASS D PATCHES, TYPE II, 7 1/4 INCH	SO YD	98	98	0				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	0					X4420000	CLASS D PATCHES, TYPE III, 7 1/4 INCH	SO YD	292	292	0				
67100100	MOBILIZATION	L SUM	1	0.5	0.5					X4420007	CLASS D PATCHES, TYPE II, 7 1/2 INCH	SO YD	75	0	75				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.5	0.5					X4420002	CLASS D PATCHES, TYPE III, 7 1/2 INCH	SO YD	225	0	225				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	0														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1872	963	909														
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	182	182	0														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7859	4328	3531														
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	533	533	0														
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	390	390	0														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	136	71	65														

\* SPECIALTY ITEM  
NP= Non-participating

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
31st STREET  
IL 171 TO DES PLAINES AVE.