

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2711	D-RS-3	LAKE	40	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN							
			TOTAL QUANTITIES 100% FED.	I 000						
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	140	140						
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	150	150						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	52	52						
40600300	AGGREGATE (PRIME COAT)	TON	260	260						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	50	50						
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	380	380						
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	140	140						
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	610	610						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	35	35						
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	13133	13133						
42001300	PROTECTIVE COAT	SO YD	100	100						
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	130	130						
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	140	140						
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	126290	126290						
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	3810	3810						
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	555	555						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2500	2500						
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	3015	3015						
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1705	1705						
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	750	750						
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	560	560						
60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	2	2						
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	6	6						
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	10	10						

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN							
			TOTAL QUANTITIES 100% FED.	I 000						
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	22	22						
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 24	FOOT	2500	2500						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12						
67100100	MOBILIZATION	L SUM	1	1						
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1						
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1						
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	15000	15000						
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	800	800						
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	71000	71000						
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4650	4650						
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	450	450						
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1250	1250						
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1210	1210						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5000	5000						
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	800	800						
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	71000	71000						
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4650	4650						
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1250	1250						
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1210	1210						
* 78000845	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 8 INCH	FOOT	450	450						
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1500	1500						

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
IL 131

1/13/2009 10:58:40 AM C:\p1001\60E93\60E93-131.dwg