

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY I000				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	88	88				
40600300	AGGREGATE (PRIME COAT)	TON	220	220				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	55	55				
40600895	CONSTRUCTING TEST STRIP	EACH	3	3				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	985	985				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	441	441				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	10780	10780				
42001300	PROTECTIVE COAT	SQ YD	1190	1190				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	5160	5160				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	110000	110000				
44000600	SIDEWALK REMOVAL	SQ FT	5160	5160				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	5350	5350				
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	230	230				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	2624	2624				
44003100	MEDIAN REMOVAL	SQ FT	60	60				
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	1275	1275				
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	10	10				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1570	1570				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	260	260				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	405	405				
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	46	46				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	197	197				
60404940	FRAMES AND GRATES, TYPE 23	EACH	1	1				

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY I000				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	17	17				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	131	131				
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	230	230				
60624600	CORRUGATED MEDIAN	SQ FT	60	60				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	17020	17020				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1350	1350				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	35300	35300				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	7650	7650				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	320	320				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1800	1800				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5700	5700				
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1350	1350				
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	35300	35300				
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	7650	7650				
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	320	320				
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1800	1800				
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1440	1440				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1440	1440				

* SPECIALTY ITEMS
NP = Non-participating

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

1/10/2009 1:28:30 PM C:\WORK\PROJECTS\GREENPOND\DOT\103RS-3\SUMMARY.QSO