

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE I000-2A URBAN
CODE NO	ITEM	UNIT		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	44	44
40600300	AGGREGATE (PRIME COAT)	TON	222	222
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	50	50
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,280	1,280
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	233	233
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	301	301
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5,427	5,427
42001300	PROTECTIVE COAT	SQ YD	1,961	1,961
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	100	100
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	42,353	42,353
44000600	SIDEWALK REMOVAL	SQ FT	100	100
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	5,520	5,520
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1,790	1,790
44003100	MEDIAN REMOVAL	SQ FT	12,778	12,778
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	1,826	1,826
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1,550	1,550
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	110	110
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	130	130
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	20	20
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	380	380
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	145	145
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	430	430
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	90	90
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	1,829	1,829
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	18	18
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	21	21
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	22	22
60404900	FRAMES AND GRATES, TYPE 12	EACH	2	2
60404950	FRAMES AND GRATES, TYPE 24	EACH	2	2
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2

SUMMARY OF QUANTITIES			URBAN 100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE I000-2A URBAN
CODE NO	ITEM	UNIT		
60620354	CONCRETE MEDIAN, TYPE SB-9 (DOWELLED)	SQ FT	2,732	2,732
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	27,000	27,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	983	983
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	28,000	28,000
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,150	2,150
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,250	1,250
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	620	620
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	430	430
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	17,203	17,203
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	983	983
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	28,000	28,000
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,150	2,150
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,250	1,250
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	620	620
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	430	430
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	755	755
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	641	641
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,064	1,064
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	160	160
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,326	2,326
X4421000	PARTIAL DEPTH PATCHING	TON	103	103
X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	612	612
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	61	61
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

© 20076600 TRAINEES HOUR 500 500

NP = Non-participating  
\* SPECIALTY ITEM  
© Y080