

**SUMMARY OF QUANTITIES**

CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				ROADWAY	SAFTEY	BRIDGES		ELECTRICAL	
						J000-2A	SFTY-3N		26TH STREET OVER FRANKLIN CONNECTOR (SN 016-1064) X231-2A
48203053	HOT-MIX ASPHALT SHOULDERS, 14"	SQ YD	239	239					
50101600	REMOVAL OF EXISTING SUPERSTRUCTURES	L SUM	1			0.5	0.5		
50102400	CONCRETE REMOVAL	CU YD	511			291	220		
50157300	PROTECTIVE SHIELD	SQ YD	2,836			1,756	1,080		
50200100	STRUCTURE EXCAVATION	CU YD	1,315			1,315			
50300225	CONCRETE STRUCTURES	CU YD	808			408	400		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	813			528	285		
50300260	BRIDGE DECK GROOVING	SQ YD	1,880			1,060	820		
50300300	PROTECTIVE COAT	SQ YD	2,686			1,636	1,050		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			0.5	0.5		
50500505	STUD SHEAR CONNECTORS	EACH	7,815			4,710	3,105		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	220,940			131,620	89,320		
50800515	BAR SPLICERS	EACH	791			706	85		
50901730	BRIDGE FENCE RAILING	FOOT	388			388			
51500100	NAME PLATES	EACH	2			1	1		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	226			138	88		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	35			22	13		
52100530	ANCHOR BOLTS, 1 1/4"	EACH	96			88	8		
52100540	ANCHOR BOLTS, 1 1/2"	EACH	26				26		
55100300	STORM SEWER REMOVAL 8"	FOOT	69	69					
58700300	CONCRETE SEALER	SQ FT	11,370			7,130	4,240		
59000200	EPOXY CRACK INJECTION	FOOT	186			162	24		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	605			345	260		
60109584	PIPE UNDERDRAINS FOR STRUCTURES 8"	FOOT	113			67	46		
60202505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	5	5					
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2					
60500040	REMOVING MANHOLES	EACH	1	1					
60500050	REMOVING CATCH BASINS	EACH	5	5					
60500060	REMOVING INLETS	EACH	5	5					
60603800	CONCRETE COMBINATION CURB AND GUTTER, TYPE B-6.12	FOOT	162	162					
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	25		25				
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2		2				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	2		2				
63200310	GUARDRAIL REMOVAL	FOOT	127		127				
63700155	CONCRETE BARRIER, SINGLE FACE, 32 INCH HEIGHT	FOOT	323		323				
63700900	CONCRETE BARRIER BASE	FOOT	323		323				

S00-02

FILE NAME = p:\2008\01\15800\cadd\Sheet\S00-1.dgn	DESIGNED - TAI	REVISED -	F.A.P. 392 FRANKLIN CONNECTOR (AT 26th STREET AND AT I-55 FRONTAGE ROAD B)		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - TAI	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		392	1717.2-3B-R	COOK	114	5
PLOT DATE = 1/12/2009	CHECKED - TWB	REVISED -			SUMMARY OF QUANTITIES		CONTRACT NO. 62197		
	DATE - 01/13/09	REVISED -	SCALE: NONE		SHEET NO.	OF	SHEETS	STA.	TO STA.
					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

\*Specialty Items