

ROADWAY REMOVAL ITEMS

EARTHWORK ITEMS

STATION TO STATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION (CU YD)
26TH STREET 10+53 10+81 12+83 13+19		
FRONTAGE ROAD B 83+78 84+14 86+91 87+30	8	72
TOTAL	8	72

STATION TO STATION	HOT-MIX ASPHALT SURFACE REMOVAL, 2" (SQ YD)	PAVEMENT REMOVAL (SQ YD)	COMBINATION CURB & GUTTER REMOVAL (FOOT)	SIDEWALK REMOVAL (SQ FT)	APPROACH SLAB REMOVAL (SQ YD)	CONCRETE MEDIAN SURFACE REMOVAL (SQ FT)	PAVED SHOULDER REMOVAL (SQ YD)	GUARDRAIL REMOVAL (FOOT)	CHAIN LINK FENCE REMOVAL (FOOT)	CONCRETE BARRIER REMOVAL (FOOT)
26TH STREET 10+53 10+81 12+83 13+19		44 74	69 118	259 783	112 121					
FRONTAGE ROAD B 83+78 84+14 86+91 87+30	138	20 51	75 100		76 135	320		127	87	
22ND STREET RAMP NORTHBOUND SOUTHBOUND							121 118			163 160
TEMP. PAVEMENT		27								
TOTAL	138	216	352	1042	444	320	239	127	87	323

ROADWAY PAVEMENT ITEMS

STATION TO STATION	SUB-BASE GRANULAR MATERIAL, TYPE B 6" (SQ YD)	SUB-BASE GRANULAR MATERIAL, TYPE B 10" (SQ YD)	SUB-BASE GRANULAR MATERIAL, TYPE B 10" (SQ YD)	PORTLAND CEMENT CONCRETE BASE COURSE, 9" (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (TON)	LEVELING BINDER (MACHINE METHOD), N70 1" (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 2" (TON)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 2" (TON)	BRIDGE APPROACH PAVEMENT (SQ YD)	PROTECTIVE COAT (SQ YD)	BRIDGE APPROACH PAVEMENT (SPECIAL) (SQ YD)	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) (SQ YD)	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH (SQ FT)	HOT-MIX ASPHALT SHOULDER, 6" (SQ YD)	HOT-MIX ASPHALT SHOULDER, 14" (SQ YD)
26TH STREET 10+53 10+81 12+83 13+19	40 31	113 160		4 8		0.1		0.1	160	183 280	113	40 31	266 798		
FRONTAGE ROAD B 83+78 84+14 86+91 87+30	16 31	91 154			0.27		1.3 0.3		91	106 184		16 30		83	
22ND STREE RAMP NORHTBOUND SOUTHBOUND				121 118											121 118
TOTAL	117	518	239	12	0.3	0.1	1.6	0.1	251	753	267	117	1064	83	239

ROADWAY PAVEMENT ITEMS CONTINUED

STATION TO STATION	COMBINATION CURB AND GUTTER, TYPE B-6.12 (FOOT)	CONCRETE BARRIER SINGLE FACE, 32" HEIGHT (FOOT)	CONCRETE BARRIER BASE (FOOT)	CHAIN LINK FENCE, 6' (FOOT)	SAND CUSHION, 3 INCH (CU YD)	DETECTABLE WARNING TILES (SQ FT)
26TH STREET 10+53 10+81 12+83 13+19	55 45				2 8	40 20
FRONTAGE ROAD B 83+78 84+14 86+91 87+30	12 49			87		
22ND STREE RAMP NORHTBOUND SOUTHBOUND		163 160	163 160			
TOTAL	162	323	323	87	10	60

SAFETY ITEMS

ALIGNMENT	STA	STA	OFFSET	TR BAR TRM T1 SPL TAN	TRAF BAR TERM T6	SPBGR TY A	GUARDRAIL MKR TYPE A	TERMINAL MARKER - DA
FRONTAGE ROAD B	83+24	84+31	RIGHT	1	1	25	3	1
FRONTAGE ROAD B	83+30	84+02	LEFT	1	1	0	2	1

TREE REMOVAL (6-15 UNITS DIAMETER)

LOCATION	STATION	OFFSET	UNIT
26TH STREET	13+88.80	37.13 RT.	12
26TH STREET	13+16.70	38.24 RT.	6
26TH STREET	13+19.30	39.98 RT.	8
26TH STREET	13+20.70	39.71 RT.	10
26TH STREET	13+22.20	43.07 RT.	10
26TH STREET	13+23.50	44.90 RT.	10
TOTAL			56

TREE REMOVAL (OVER 15 UNITS DIAMETER)

LOCATION	STATION	OFFSET	UNIT
26TH STREET	10+60.40	41.73' LT.	20
26TH STREET	12+91.20	36.29' LT.	18
TOTAL			38

SCH-01