

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"						
LOCATION	FROM STATION	TO STATION	SKIP DASH	COLOR	LANES	FOOT
BRIDGE MEDIAN	11+11.70	13+17.00	N/A	YELLOW		836.1
TOTAL=						836

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70							112 LBS/SQ YD/IN
FROM STATION	TO STATION	SO FT	THICKNESS (IN)	LOCATION	TON		
10+20.00	10+79.00	7496.32	1.50	WEST INTERSECTION	70.0		
13+22.25	14+75.00	16233.7	1.50	EAST INTERSECTION	151.5		
10+78.99	10+85.25	591.82	1.50	PAVEMENT CONNECTOR	5.5		
13+11.82	13+22.25	667.32	1.50	PAVEMENT CONNECTOR	6.2		
TOTAL=						233	

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 6"			
LOCATION	FROM STATION	TO STATION	FOOT
WB 111TH BRIDGE	11+15.20	12+91.03	175.8
EB 111TH BRIDGE	11+38.71	13+04.00	165.29
TOTAL=			341

LEVELING BINDER (MACHINE METHOD), N70							112 LBS/SQ YD/IN
FROM STATION	TO STATION	SO FT	THICKNESS (IN)	LOCATION	TON		
10+20.00	10+79.00	7496.32	1.00	WEST INTERSECTION	46.6		
13+22.25	14+75.00	16233.7	1.00	EAST INTERSECTION	101.0		
10+78.99	10+85.25	591.82	1.00	PAVEMENT CONNECTOR	3.7		
13+11.82	13+22.25	667.32	1.00	PAVEMENT CONNECTOR	4.2		
TOTAL=							

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 12"		
LOCATION	FOOT	
DIAGONALS MEDIAN 112TH BRIDGE	100.0	
TOTAL=		100

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12						
FROM STATION	TO STATION	RT/LT	LOCATION	FOOT		
10+16.31	10+07.49	RT	SW CORNER 111 & MARSHFIELD	17.5		
10+56.91	10+44.28	LT	NW CORNER 111 & MARSHFIELD	19.3		
10+68.29	10+76.88	RT	SE CORNER 111 & MARSHFIELD	25.0		
10+99.85	10+97.21	LT	NE CORNER 111 & MARSHFIELD	24.7		
13+03.23	13+24.82	RT	SW CORNER 111 & HAMLET	49.0		
13+22.73	13+65.52	LT	NW CORNER 111 & MARSHFIELD	79.0		
14+04.49	14+24.32	LT	NE CORNER 111 & HAMLET	26.0		
13+69.87	13+91.82	RT	SE CORNER 111 & HAMLET	27.2		
TOTAL DAMAGED FROM ITEM 44000500 (C&G REMOVAL)					150.0	
TOTAL=						418

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 24"		
LOCATION	STATION	FOOT
111TH BRIDGE	11+19.30	28.0
111TH BRIDGE	13+00.70	28.0
111TH BRIDGE	RAILROAD BARS	52.0
TOTAL=		108

SELECTIVE CLEARING			1 UNIT/1000 SQ FT
LOCATION	SO FT	UNIT	
NB I-57 OUTSIDE SHLDR (SOUTH)	424.74	0.42	
NB I-57 OUTSIDE SHLDR (NORTH)	254.86	0.25	
TOTAL=			1

BARRIER WALL MARKERS, TYPE C				
LOCATION	FOOT	SPACING (FT)	EACH	
MARSHFIELD RD	270.0	25	22	
OUTSIDE SB I-57	270.0	25	22	
INSIDE SB I-57	290.0	25	23	
INSIDE NB I-57	270.0	25	22	
OUTSIDE NB I-57	270.0	25	22	
HAMELET AVE	230.0	25	18	
TOTAL=				128

PAVEMENT MARKING REMOVAL					
LOCATION	DESCRIPTION	FROM STATION	TO STATION	WIDTH (FT)	SO FT
W. OF R.R. TRACKS	R.R. CROSSING	8+35.98	8+85.98		101.2
W. OF R.R. TRACKS	MEDIAN STRIPPING	8+15.35	9+72.38	0.3	199.3
W. OF R.R. TRACKS	MEDIAN STRIPPING	8+15.35	9+72.38	1.0	22.0
W. OF R.R. TRACKS	EB LANE 6'-18'	8+15.35	9+35.13	0.3	9.9
W. OF R.R. TRACKS	WB LANE 6'-18'	8+15.35	9+66.13	0.3	12.4
W. OF R.R. TRACKS	EB STOP BAR	9+35.13		2.0	48.0
EB OF R.R. TRACKS	MEDIAN STRIPPING	9+91.81	10+21.63	0.3	42.6
EB OF R.R. TRACKS	MEDIAN STRIPPING	9+91.81	10+21.63	1.0	15.0
MARSHFIELD/111TH	N. CROSSWALK	10+41.02	10+98.76	0.5	57.7
MARSHFIELD/111TH	S. CROSSWALK	9+99.38	10+74.05	1.5	224.0
RAMP D	STOP BAR	0+15.08		2.0	81.4
RAMP D	LANE LINE	0+20.33	0+43.24	0.3	7.6
RAMP D	LANE LINE	0+22.91	0+43.24	0.3	6.7
111 TH STREET	MEDIAN STRIPPING	14+75.00	15+93.26	0.3	114.6
112 TH STREET	MEDIAN STRIPPING	14+75.00	15+27.58	1.0	20.0
TOTAL=					963

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
111TH STREET OVER  
F.A.I. ROUTE 57 (INTERSTATE 57)

**SCHEDULE OF QUANTITIES**

SCALE: N.T.S. DRAWN BY: BRH  
DATE: 01/16/09 CHECKED BY: ACL

**TENG**  
TENG & ASSOCIATES, INC.  
ENGINEERS, ARCHITECTS, PLANNERS  
205 N. MICHIGAN AVE., CHICAGO, IL 60601  
TELEPHONE: 312/916-0000

F:\DOCUMENTS\309660\CIVIL\DRAWING\SC0000\J00.DGN  
 1-6-2009, 14:42:49  
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63