

SUMMARY OF QUANTITIES

CODE NO.	ITEM	URBAN UNIT	TOTAL QUANTITY	100% FED. URBAN	ROADWAY	BRIDGE	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS	CONSTRUCTION TYPE CODE							
				X771-2A													
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	70		70												
20101000	TEMPORARY FENCE	FOOT	500		500												
20101100	TREE TRUNK PROTECTION	EACH	20		20												
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	201			201											
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	0.4		0.4												
25000210	SEEDING, CLASS 2A	ACRE	0.4		0.4												
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	36		36												
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	36		36												
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	36		36												
25100630	EROSION CONTROL BLANKET	SQ YD	1996		1996												
28000400	PERIMETER EROSION BARRIER	FOOT	547		547												
28000510	INLET FILTERS	EACH	4		4												
31200100	STABILIZED SUB-BASE 4"	SQ YD	44		44												
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	44		44												
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5		5												
40600300	AGGREGATE (PRIME COAT)	TON	13		13												
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.7		0.7												
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	367		367												
40600895	CONSTRUCTING TEST STRIP	EACH	2		2												
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	551		551												
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	5		5												
42001300	PROTECTIVE COAT	SQ YD	305		305												
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	370		370												
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	132		132												
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	1993		1993												
42400800	DETECTABLE WARNINGS	SQ FT	111		111												
44000100	PAVEMENT REMOVAL	SQ YD	143		143												
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	6561		6561												
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	436		436												
44000600	SIDEWALK REMOVAL	SQ FT	1995		1995												
44000700	APPROACH SLAB REMOVAL	SQ YD	368		368												

• DENOTES SPECIALTY ITEMS
 NON-PARTICIPATING

BRIDGE INFORMATION

① 112TH PL. OVER NB & SB I-57 S.N. 016-0988

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 112TH PLACE OVER
 F.A.I. ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
 DATE: 01/16/09 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 205 N. MICHIGAN AVE. CHICAGO, IL 60601
 TELEPHONE: 312/616-0000

ATTENTION: \S\000056\000056.DGN, \S\000056\000056.DGN
 H-6-2009, 06:56:05
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63