

COMBINATION CURB AND GUTTER REMOVAL				
FROM STATION	TO STATION	RT/LT	LOCATION	FOOT
12+88.00	12+97.00	RT	SE CORNER 112 & MARSHFIELD	23.0
13+23.23	13+24.23	RT	NE CORNER 112 & MARSHFIELD	20.0
15+36.66	15+46.95	LT	SW CORNER 112 & HAMLET	69.0
15+35.74	15+81.87	LT	NW CORNER 112 & HAMLET	58.0
12+46	12+40	RT	SW CORNER 112 & MARSHFIELD	34.5
12+69	12+57	LT	NW CORNER 112 & MARSHFIELD	20.3
15+99	16+08	RT	SE CORNER 112 & HAMLET	16.1
16+28	16+47	LT	NE CORNER 112 & HAMLET	45.6
DAMAGED CURB AND GUTTER DETERMINED BY THE ENGINEER				150.0
TOTAL=				436

SIDEWALK REMOVAL				
FROM STATION	TO STATION	SO FT	LOCATION	SO FT
12+89.51	13+19.00	231.2	SE CORNER 112 & MARSHFIELD	231.2
13+25.16	13+39.29	157.3	NE CORNER 112 & MARSHFIELD	157.3
14+95.62	15+45.65	499.0	SW CORNER 112 & HAMLET	499.0
15+15.69	15+80.35	470.1	NW CORNER 112 & HAMLET	470.1
12+42.84	12+33.32	177.58	SW CORNER 112 & MARSHFIELD	177.6
12+71.79	12+57.16	118.83	NW CORNER 112 & MARSHFIELD	118.8
15+98.84	16+15.07	120.21	SE CORNER 112 & HAMLET	120.2
16+28.45	16+46.88	220.41	NE CORNER 112 & HAMLET	220.4
TOTAL=				1995

APPROACH SLAB REMOVAL			
FROM STATION	TO STATION	SQ FT	SQ YD
13+08.70	13+29.10	1394.2	154.9
15+05.57	15+34.80	1919.1	213.2
TOTAL=			368

MEDIAN REMOVAL		
FROM STATION	TO STATION	SQ FT
16+20.00	17+31.00	400.0
TOTAL=		400.0

STRIP REFLECTIVE CRACK CONTROL TREATMENT				
FROM STATION	TO STATION	SQ FT	LOCATION	FOOT
15+70.00	16+44.00	2.00	FRONTAGE ROAD "B"	148.0
0+00.00	9+00.00	2.00	HAMELT AVE	1800.0
15+80.37	16+57.00	2.00	FRONTAGE ROAD "A"	153.3
0+00.00	1+79.15	2.00	MARSHFIELD AVE	358.3
TOTAL=				2460

TEMPORARY PAVEMENT MARKING- LETTERS AND SYMBOLS				
LOCATION	DESCRIPTION	SQ FT	LANES	SQ FT
WB 112TH AT HAMLET	RT TURN ARROW	15.2	2.00	30.4
EB 112TH AT MARSHFIELD	RT TURN ARROW	15.2	2.00	30.4
TOTAL=				61

TEMPORARY PAVEMENT MARKING - LINE 4"		
LOCATION	FOOT	
MARSHFIELD RD NEXT TO TEMPORARY BARRIER WALL	272.0	
HAMELT AVE NEXT TO TEMPORARY BARRIER WALL	230.0	
TOTAL=		502

TEMPORARY PAVEMENT MARKING - LINE 6"			
FROM STATION	TO STATION	LOCATION	FOOT
16+50.00	17+31.00	WB 112TH	81.0
11+36.95	11+80.64	EB 112TH	43.7
		CONCRETE BARRIER WALL MARSHFIELD RD	270.0
		CONCRETE BARRIER WALL OUTSIDE SB I-57	270.0
		CONCRETE BARRIER WALL INSIDE SB I-57	290.0
		CONCRETE BARRIER WALL INSIDE NB I-57	270.0
		CONCRETE BARRIER WALL OUTSIDE NB I-57	270.0
		CONCRETE BARRIER WALL HAMELET AVE	230.0
TOTAL=			1725

WORK ZONE PAVEMENT MARKING REMOVAL		
PAY ITEM #	PAY ITEM	FOOT
70300100	SHORT-TERM PAVEMENT MARKING	289.1
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	61.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	165.7
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	862.5
TOTAL=		1378

TEMPORARY CONCRETE BARRIER		
LOCATION	FOOT	
MARSHFIELD RD	270.0	
OUTSIDE SB I-57	270.0	
INSIDE SB I-57	290.0	
INSIDE NB I-57	270.0	
OUTSIDE NB I-57	270.0	
HAMELET AVE	230.0	
TOTAL=		1600

THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS				
LOCATION	DESCRIPTION	SQ FT	SIZE	SQ FT
SB MARSHFIELD AVE	RT ARROW ONLY	36.4	LARGE	36.4
SB MARSHFIELD AVE	LT ARROW ONLY	36.4	LARGE	36.4
112TH WEST OF R.R.	RT ARROW ONLY	36.4	LARGE	36.4
112TH EAST OF R.R.	RT ARROW ONLY	15.6	LARGE	15.6
FRONTAGE RD B	LT ARROW ONLY	36.4	LARGE	36.4
FRONTAGE RD B	LT THRU ARROW ONLY	46.8	LARGE	46.8
FRONTAGE RD B	RT THRU ARROW ONLY	46.8	LARGE	46.8
TOTAL=				255

STABILIZED SUB-BASE 4"			
FROM STATION	TO STATION	SQ FT	SQ YD
16+20.00	17+31.00	400.0	44.44
TOTAL=			44

THERMOPLASTIC PAVEMENT MARKING - LINE 4"							
LOCATION	FROM STATION	TO STATION	SKIP DASH	COLOR	LANES	FOOT	
MARSHFIELD AVE	0+52.62	1+79.25	6'-18'	WHITE	1.00	31.7	
FRONTAGE RD A	15+80.37	16+15.00	6'-18'	WHITE	2.00	17.3	
HAMELT AVE	0+41.00	9+00.00	6'-18'	WHITE	2.00	429.5	
EB 112TH	11+38.75	12+27.25	6'-18'	WHITE	1.00	22.1	
WB 112TH	11+38.75	12+27.25	6'-18'	WHITE	1.00	22.1	
WB 112TH	16+50.00	17+31.00	6'-18'	WHITE	1.00	20.3	
MARSHFIELD AVE	0+58.00	1+79.25	N/A	YELLOW		121.3	
FRONTAGE RD A	15+80.37	16+21.50	N/A	YELLOW		41.1	
HAMELT AVE	0+36.00	9+00.00	N/A	YELLOW		864.0	
FRONTAGE RD B	15+70.00	15+93.00	N/A	YELLOW		23.0	
MEDIAN W. R.R.	11+35.00	11+94.00	N/A	YELLOW		240.0	
MEDIAN E. R.R.	12+16.00	12+43.00	N/A	YELLOW		105.0	
MEDIAN HAMLET/112TH	16+36.00	17+31.00	N/A	YELLOW		388.0	
RAILROAD DIAGONALS				WHITE		165.0	
TOTAL=						2490	

THERMOPLASTIC PAVEMENT MARKING - LINE 6"					
LOCATION	FROM STATION	TO STATION	FOOT	LANES	FOOT
MARSHFIELD AVE	0+52.62	1+79.25	126.6	2.00	253.3
FRONTAGE RD B	15+45.00	15+98.00	53.0	2.00	106.0
CROSSWALK MARSH/112TH			358.0		358.0
CROSSWALK HAMLET/112TH			367.0		367.0
TOTAL=					1084

THERMOPLASTIC PAVEMENT MARKING - LINE 12"		
LOCATION	FOOT	
MEDIAN DIAGONALS MARSHFIELD/112TH	45.0	
MEDIAN DIAGONALS HAMLET/112TH	75.0	
RAILROAD STRIPE	24.0	
TOTAL=		144

THERMOPLASTIC PAVEMENT MARKING - LINE 24"		
LOCATION	STATION	FOOT
SB MARSHFIELD	0+46.41	45.0
NB FRONTAGE RD B	16+03.92	39.0
EB 112TH	11+74.88	25.0
WB 112TH	12+41.31	25.0
WB 112TH	16+52.76	22.0
TOTAL=		156

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
112TH PLACE OVER  
F.A.I. ROUTE 57 (INTERSTATE 57)

### SCHEDULE OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH  
DATE: 01/16/09 CHECKED BY: ACL

**TENG**  
TENG & ASSOCIATES, INC.  
ENGINEERS/ARCHITECTS/PLANNERS  
205 N. MICHIGAN AVE., CHICAGO, IL 60601  
TELEPHONE: 312/516-5000

..\TTC000M\LDON.. \SC0000\LDON  
 H6-2009\_134557  
 T:\DOCUMENT\930860\KIVL\DRN\SC0000\LDON  
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63  
 HECHTBR