

SCHEDULE OF QUANTITIES

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION	REMARKS
I-74		
396	LT Sta 52+73.21 - 211+ 24.79	One-way Crystal -- Double Markers
396	RT Sta 52+73.21 - 211+ 24.79	One-way Crystal -- Double Markers
13	LT Sta 64+76.71 - 70+ 12.84	One-way Crystal @ 40' o.c.
16	LT Sta 125+15.45 - 128+ 37.61	One-way Crystal @ 40' o.c.
21	RT Sta 175+15.02 - 179+ 37.42	One-way Crystal @ 40' o.c.
9	RT Sta 186+82.72 - 188+ 63.76	One-way Crystal @ 40' o.c.
9	RT Sta 191+90.47 - 192+ 61.94	One-way Crystal @ 40' o.c.
862	SUB-TOTAL	
I-74 / IL 5 (JOHN DEERE RD.) INTERCHANGE		
Ramp "A"		
4	LT Sta 184+92.56 - 186+ 63	One-way Crystal @ 40' o.c.
8	LT Sta 4+88.07 - 6+ 55.77	One-way Crystal @ 20' o.c.
13	SUB-TOTAL	
Ramp "B"		
4	RT Sta 16+61.00 - 17+ 43.07	One-way Crystal @ 20' o.c.
2	LT Sta 179+71.74 - 180+ 62.78	One-way Crystal @ 40' o.c.
6	SUB-TOTAL	
Ramp "C"		
9	LT Sta 190+25.00 - 191+ 97.97	One-way Crystal @ 40' o.c.
9	SUB-TOTAL	
Ramp "D"		
11	LT Sta 201+32.31 - 205+ 53.14	One-way Crystal @ 40' o.c.
21	RT Sta 67+91.55 - 72+ 03.53	One-way Crystal @ 20' o.c.
31	SUB-TOTAL	
Ramp "E"		
10	RT Sta 191+90.47 - 192+ 61.94	One-way Crystal @ 20' o.c.
10	SUB-TOTAL	
Ramp "F"		
5	RT Sta 191+90.47 - 192+ 61.94	One-way Crystal @ 40' o.c.
5	SUB-TOTAL	
Ramp "G"		
18	RT Sta 186+82.72 - 188+ 63.76	One-way Crystal @ 20' o.c.
18	SUB-TOTAL	
Ramp "H"		
21	Sta 175+15.02 - 179+ 37.42	One-way Crystal @ 20' o.c.
21	SUB-TOTAL	
974	TOTAL	

78201000 TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION
I-74 / IL ROUTE 5 INTERCHANGE	
Ramp B	
1	LT Sta 23+40.50
1	TOTAL

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION	REMARKS
I-74		
100	LT Sta 65+97 - 211+ 30	Inbetween Drivng & Passing Lanes
107	RT Sta 64+00 - 211+ 30	Inbetween Drivng & Passing Lanes
208	SUB-TOTAL	
I-74 / IL ROUTE 5 INTERCHANGE		
13	Ramp A	
3	Ramp B	
1	Ramp C	
48	Ramp D	
17	Ramp E	
23	Ramp G	
246	Ramp H	
139	SUB-TOTAL	
347	TOTAL	

88600400 DETECTOR LOOP, SPECIAL

EQOT	LOCATION	REMARKS
I-74 / 23RD (AVENUE OF CITIES) INTERCHANGE		
Northwest Ramp		
1,124	RT Sta 121+39.31 - 121+ 85.31	2 Total "6' x 20' Loops"
	Sta 61+94 - 62+ 00	3 Total "6' x 6' Loops"
	Sta 64+84.5 - 65+ 30.5	8 Total "6' x 20' Loops"
1,124	RT Sta 65+10.11 - 65+ 30.11	6' x 20' Loop-RT Turn Lane
	SUB-TOTAL	
Southeast Ramp		
1,143	RT Sta 124+60.68 - 125+ 06.68	2 Total "6' x 20' Loops"
	Sta 538+27.83 - 538+ 73.83	6 Total "6' x 20' Loops"
	LT Sta 538+35.57 - 538+ 55.57	6' x 20' Loop-RT Turn Lane
	Sta 541+57.83 - 541+ 63.83	3 Total "6' x 6' Loops"
1,143	SUB-TOTAL	
2,267	TOTAL	

X0324914 SLOTTED DRAINS TO BE ADJUSTED

EQOT	LOCATION	REMARKS
111	LT Sta 201+47.64 - 202+ 58.35	65.23' to 58.46' LT o/s Respectively
111	TOTAL	

X6310195 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT), MODIFIED

EACH	LOCATION
I-74 / IL ROUTE 5 INTERCHANGE	
Ramp B	
1	LT Sta 22+90.5 - 23+ 40.5
1	TOTAL

Z0028415 GEOTECHNICAL REINFORCEMENT

SQ YD	LOCATION
447	5% Contingency of all Patchhg Locatbns on Project
447	TOTAL

Z0028700 GRANULAR SUBGRADE REPLACEMENT

CU YD	LOCATION
149	5% Contingency of all Patchhg Locatbns on Project
149	TOTAL