

# SUMMARY OF STRUCTURAL PLANS

CODE NUMBER	ITEM	UNIT	SN 081-0099	SN 081-0100	SN 081-0101	SN 081-0102	SN 081-0103	SN 081-0104	SN 081-0105	SN 081-0108	SN 081-0109	SN 081-0110	TOTALS
28100101	STONE RIPRAP, CLASS A1	SQ YD	---	---	---	---	---	---	---	29.9	---	---	30
40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	252.00	268.00	102.00	74.00	122.00	96.00	348.00	---	862.00	66.60	2,191
50102400	CONCRETE REMOVAL	CU YD	37.5	37.5	16.2	12.4	29.9	21.8	27.3	17.6	16.6	15.8	232.6
50104650	SLOPE WALL REMOVAL	SQ YD	---	---	---	---	---	---	554	---	---	---	554
50157300	PROTECTIVE SHIELD	SQ YD	1,011	820	354	252	305	232	1,179	---	354	330	4,837
50300255	CONCRETE SUPERSTRUCTURE	CU YD	37.5	37.5	16.2	12.4	29.9	21.8	27.3	17.6	16.6	15.8	232.6
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4530	4580	1,850	1,390	2,720	2,100	3,770	2,170	2,230	2,080	27,420
50800515	BAR SPLICERS	EACH	70	70	22	22	22	22	44	22	22	22	338
51100100	SLOPE WALL 4 INCH	SQ YD	---	---	---	---	---	---	554	---	---	---	554
52000110	PREFORMED JOINT STRIP SEAL	FOOT	170	170	117	86	184	139	240	112	114	107	1,439
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	2,245	2,389	570.7	414.3	1,170	924.0	2,340.0	---	799.2	746.2	11,598
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	---	---	---	---	---	---	---	1.0	---	---	1.0
60100945	PIPE DRAINS 12"	FOOT	---	---	---	---	---	---	---	---	15	---	15
63300405	REMOVAL AND REINSTALLATION OF EXISTING TRAFFIC BARRIER TERMINAL, TYPE I	EACH	3	3	---	---	---	---	---	---	---	---	6
X0301424	SILICONE JOINT SEALER	FOOT	---	---	---	---	---	---	234	14	---	---	248
X0321316	ACCESS DOOR	EACH	---	---	---	---	---	---	---	2	---	---	2
X0324865	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	2,245	2,389	570.7	414.3	1,170	924	2,340	---	799.2	746.2	11,598
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	---	---	---	---	---	---	162	---	18	27	207
Z0006200	BRIDGE DECK SCARIFICATION	SQ YD	2,323	2,466	564.5	409.8	1,160	917	2,330	---	793.1	740.5	11,704
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	25	25	32	22.7	162.5	25	---	---	47.5	70	410
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	400	500	32	22.7	162.5	25	3	---	47.5	70	1,263
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	450	450	64	50.5	120	120	27	---	10	20	1,312
Z0032470	JOINT SEALER	FOOT	---	---	---	---	---	---	---	62	---	---	62