

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

100% FEDERAL

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	(115)RS-1	LIVINGSTON	279	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 66375				

SUMMARY OF QUANTITIES				CONSTRUCTION CODE			
				I 000	SFTY-1B	Y060	Y079
CODE NO.	ITEM	UNIT	TOTAL QTY.	ROADWAY	SIDEWALKS	HAZARD WASTE WATER MAINS	HAZARD WASTE REMEDICATION ITEMS
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	106	106			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	192	192			
20101200	TREE ROOT PRUNING	EACH	27	27			
20200100	EARTH EXCAVATION	CU YD	2,918	2,918			
20800150	TRENCH BACKFILL	CU YD	1,834	1,834			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,357	1,357			
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	500	500			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	290	290			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	290	290			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	290	290			
* 25200100	SODDING	SQ YD	23,388	23,388			
* 25200200	SUPPLEMENTAL WATERING	UNIT	210.2	210.2			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,559	1,559			
28000300	TEMPORARY DITCH CHECKS	EACH	26	26			
28000400	PERIMETER EROSION BARRIER	FOOT	755	755			
28000500	INLET AND PIPE PROTECTION	EACH	63	63			
28100209	STONE RIPRAP, CLASS A5	TON	115	115			
28200200	FILTER FABRIC	SQ YD	101	101			
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	5,342	5,342			
35101400	AGGREGATE BASE COURSE, TYPE B	TON	271	271			
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	2,073	2,073			

\* SPECIALITY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION


**SUMMARY QUANTITIES**

FAP 681 (IL RTE. 116)  
SECTION (115)RS-1  
LIVINGSTON COUNTY  
VILLAGE OF CULLOM

SCALE: VERT. \_\_\_\_\_  
          HORIZ. \_\_\_\_\_  
DATE: 11/05/03

DRAWN BY: JAMESON  
DESIGNED BY: BOTT  
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.  
OF SPRINGFIELD

 PROFESSIONAL ENGINEERS  
REGISTERED PROFESSIONAL ENGINEERS  
PROFESSIONAL SURVEYORS  
PROFESSIONAL LAND SURVEYORS  
PROFESSIONAL ARCHITECTS

COMPUTER FILE NO.  
SUMMARYP2-1

PROJECT 03145  
09/05/07-WCB