F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	(115)RS-1	LIVINGSTON	279	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 66375

100% FEDERAL

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION CODE I 000 ROADWAY	SFTY-1B SIDEWALKS	Y060 WATER MAINS	Y079 HAZARD WASTE REMEDIATION ITEMS
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,850	2,850			
40600300	AGGREGATE (PRIME COAT)	TON	46	46			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5.5	5.5			
40600525	LEVELING BINDER (HAND METHOD), N50	TON	13	13			
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,032	1,032			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	925	925			
40600990	TEMPORARY RAMP	SQ YD	368	368			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,198	1,198			
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	772	772			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	655	655			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1,834	1,834			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,025	1,025			
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	13,221		13,221		
42400610	TEMPORARY SIDEWALK	SQ FT	1,000		1,000		
42400800	DETECTABLE WARNINGS	SQ FT	410		410		
44000100	PAVEMENT REMOVAL	SQ YD	1,827	1,827			
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	1,704	1,704			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2,984	2,984			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,169	2,169			
44000300	CURB REMOVAL	FOOT	717	717			
44000600	SIDEWALK REMOVAL	SQ FT	7,943		7,943		
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	78	78			
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	316	316			
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	70	70			
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	54	54			
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	2,938	2,938			

* SPECIALITY ITEMS

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY QUANTITIES

FAP 681 (IL RTE. 116)
SECTION (115)RS-1
LIVINGSTON COUNTY
VILLAGE OF CULLOM

SCALE: VERT. HORIZ.
DATE: 11/05/03

DRAWN BY: JAMESON
DESIGNED BY: BOTT
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
1500 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM NO. 184-000175
PROFESSIONAL & STRUCTURAL ENGINEERING CORPORATION
(217) 793-3884, (217) 793-3207 (FILE) FAX, (217) 793-3884 E-MAIL: contact@greenebradford.com

COMPUTER FILE NO. SUMMARYP2-2
PROJECT 03145
09/05/07-WCB

IDOTPL-50 1"=50' 8/07/00