F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	(115)RS-1	LIVINGSTON	279	28
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 66375

SIDEWALK REMOVAL SCHEDULE

LOCATION	SIDEWALK REMOVAL SQ. FT.
MAINLINE	
STA. 159+28.00, RT TO STA. 160+82.00, RT	593
STA. 160+21.00, LT TO STA. 160+49.00, LT	110
STA. 161+32.00, LT TO STA. 161+49.62, LT	90
STA. 161+66.76, LT TO STA. 161+85.00, LT	76
STA. 162+28.00, RT. TO STA. 162+54.83, RT.	126
STA. 162+85.20, RT. TO STA. 163+15.00, RT.	126
STA. 163+00.00, LT. TO STA. 163+41.00, LT.	160
STA. 163+67.00, LT. TO STA. 164+20.00, LT.	200
STA. 163+84.00, RT. TO STA. 164+08.00, RT.	93
STA. 164+47.00, RT. TO STA. 164+72.00, RT.	100
STA. 164+72.00, RT.	27
STA. 165+63.00, RT. TO STA. 165+67.00, RT.	26
STA. 165+64.00, LT. TO STA. 165+73.00, LT.	46
STA. 165+95.00, RT. TO STA. 166+24.27, RT.	214
STA. 165+95.00, LT. TO STA. 166+24.07, LT.	189
STA. 166+49.92, LT. TO STA. 166+79.00, LT.	126
STA. 166+49.73, RT. TO STA. 166+79.00, RT.	123
STA. 168+08.00, LT. TO STA. 168+37.00, LT.	116
STA. 168+47.00, RT. TO STA. 168+78.00, RT.	124
STA. 168+61.00, LT. TO STA. 168+64.00, LT.	27
STA. 168+83.00, LT. TO STA. 169+08.00, LT.	100
STA. 169+34.00, RT. TO STA. 169+38.00, RT.	16
STA. 169+56.00, RT. TO STA. 169+90.06, RT.	350
STA. 169+67.00, LT. TO STA. 169+96.00, LT.	214
STA. 170+25.92, RT. TO STA. 170+65.00, RT.	160
STA. 170+22.00, LT. TO STA. 170+60.00, LT.	132
STA. 171+21.00, RT. TO STA. 171+45.00, RT.	95
STA. 171+63.00, LT. TO STA. 171+92.00, LT.	116
STA. 172+38.00, RT. TO STA. 172+63.00, RT.	99
STA. 172+47.00, LT. TO STA. 172+76.00, LT.	116
STA. 173+09.00, LT. TO STA. 173+13.00, LT.	32
STA. 173+22.00, RT. TO STA. 173+61.00, RT.	156
STA. 174+18.00, RT. TO STA. 174+52.00, RT.	341
STA. 174+89.00, RT. TO STA. 175+48.00, RT.	334
STA. 174+96.25, LT. TO STA. 175+39.00, LT.	195
STA. 179+23.00, RT. TO STA. 179+92.00, RT.	494
STA. 179+36.00, LT. TO STA. 179+67.00, LT.	184
STA. 180+28.00, LT. TO STA. 180+52.00, LT.	98
STA. 180+84.00, RT. TO STA. 181+48.00, RT.	261
STA. 181+16.00, LT. TO STA. 181+74.00, LT.	232
STA. 181+90.00, RT. TO STA. 182+15.00, RT.	98
STA. 182+75.00, LT. TO STA. 183+02.00, LT.	120
STA. 182+97.00, RT. TO STA. 183+24.00, RT.	113
STA. 183+54.00, RT. TO STA. 183+89.00, RT.	152
STA. 184+37.00, RT. TO STA. 184+69.00, RT.	109
STA. 185+16.00, RT. TO STA. 185+41.00, RT.	107
STA. 187+05.00, RT. TO STA. 187+33.00, RT.	119
STA. 191+70, RT.	36
STA. 194+25, RT.	34
SW QUADRANT OAK ST. AND HACK ST.	638
TOTALS	7,943

SIDEWALK SCHEDULE

LOCATION	PORTLAND CEMENT CONCRETE SIDEWALK SQ. FT.
STA. 159+28.00, RT. TO STA. 160+82.00, RT.	437
STA. 160+21.00, LT. TO STA. 160+49.00, LT.	80
STA. 161+32.00, LT. TO STA. 161+85.00, LT.	177
STA. 162+28.00, RT. TO STA. 163+15.00, RT.	281
STA. 163+00.00, LT. TO STA. 163+41.00, LT.	101
STA. 163+84.00, RT. TO STA. 164+08.00, RT.	65
STA. 164+47.00, RT. TO STA. 164+72.00, RT.	65
STA. 163+67.00, LT. TO STA. 164+20.00, LT.	179
STA. 165+95.00, RT. TO STA. 166+24.27, RT.	226
STA. 165+95.00, LT. TO STA. 166+24.07, LT.	227
STA. 166+49.92, LT. TO STA. 166+79.00, LT.	128
STA. 166+49.73, RT. TO STA. 166+79.00, RT.	129
STA. 168+08.00, LT. TO STA. 168+37.00, LT.	60
STA. 168+83.00, LT. TO STA. 169+08.00, LT.	65
STA. 168+47.00, RT. TO STA. 168+78.00, RT.	65
STA. 169+56.00, RT. TO STA. 169+90.06, RT.	329
STA. 169+67.00, LT. TO STA. 169+96.00, LT.	234
STA. 170+25.92, RT. TO STA. 170+65.00, RT.	178
STA. 170+26.00, LT. TO STA. 170+60.00, LT.	170
STA. 171+21.00, RT. TO STA. 171+45.00, RT.	60
STA. 171+63.00, LT. TO STA. 171+92.00, LT.	65
STA. 172+38.00, RT. TO STA. 172+63.00, RT.	65
STA. 172+47.00, LT. TO STA. 172+76.00, LT.	70
STA. 173+22.00, RT. TO STA. 173+61.00, RT.	100
STA. 174+16.00, LT. TO STA. 174+45.00, LT.	323
STA. 174+18.00, RT. TO STA. 174+52.00, RT.	380
STA. 174+89.00, RT. TO STA. 175+48.00, RT.	388
STA. 174+96.25, LT. TO STA. 175+39.00, LT.	379
STA. 179+23.00, RT. TO STA. 179+92.00, RT.	603
STA. 179+36.00, LT. TO STA. 179+67.00, LT.	247
STA. 180+28.00, LT. TO STA. 180+52.00, LT.	60
STA. 180+84.00, RT. TO STA. 181+48.00, RT.	145
STA. 181+16.00, LT. TO STA. 181+74.00, LT.	130
STA. 181+90.00, RT. TO STA. 182+15.00, RT.	65
STA. 182+75.00, LT. TO STA. 183+02.00, LT.	133
STA. 182+97.00, RT. TO STA. 183+24.00, RT.	126
STA. 183+54.00, RT. TO STA. 183+89.00, RT.	162
STA. 184+37.00, RT. TO STA. 184+64.00, RT.	65
STA. 185+16.00, RT. TO STA. 185+41.00, RT.	65
STA. 187+05.00, RT. TO STA. 187+33.00, RT.	126
STA. 187+62.88, RT. TO STA. 190+88.10, RT.	1,418
STA. 191+19.90, RT. TO STA. 200+00.00, RT.	4,012
SW QUADRANT OAK ST. AND HACK ST.	838
TOTAL	13,221

ADJUSTING WATER MAIN SCHEDULE

STATION	OFFSET	BOX CULVERT	STORM SEWER DIAMETER (INCHES)	FLOWLINE ELEVATION (FOOT)	ASSUMED WATERMAIN CROWN ELEVATION (FOOT)	ADJUSTING WATER MAIN 4" (FOOT)	ADJUSTING WATER MAIN 6" (FOOT)
157+06	30' LT.		12	679.15	678.30	32	
174+90	20' LT.		48	671.36	675.50		32
179+07	58' LT.	10' X 4'	12	671.19	673.36		90
TOTAL						32	122

NOTE: ASSUMES FOUR FOOT DEPTH.

TREE REMOVAL SCHEDULE

LOCATION	TREE REMOVAL (6 TO 15 DIAMETER) UNIT	TREE REMOVAL (OVER 15 DIAMETER) UNIT
MAINLINE		
STA. 166+10, 39' RT.	12	
STA. 166+72, 39' RT.	6	
STA. 180+05, 34' LT.		38
STA. 180+74, 30' LT.	12	
STA. 183+03, 34' LT.		38
STA. 187+28, 37' RT.	12	
STA. 189+32, 32' RT.		24
STA. 189+46, 37' RT.	12	
STA. 189+68, 36' RT.		15
STA. 189+93, 36' RT.		15
STA. 190+13, 38' RT.	12	
STA. 195+90, 42' LT.		20
STA. 196+59, 32' RT.	6	
STA. 197+52, 32' RT.		24
STA. 198+94, 31' RT.	12	
STA. 199+18, 32' RT.	12	
TOTAL	96	174
ADJUSTED TOTAL (10% INCREASE)	106	192

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

REVISIONS	
NAME	DATE
IDOT REV. - WCB	10/08

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP 681 (IL RTE. 116)
SECTION (115)RS-1
LIVINGSTON COUNTY
VILLAGE OF CULLOM

SCALE: VERT. HORIZ.
DATE: 11/05/03

DRAWN BY: JAMESON
DESIGNED BY: BOTT
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
SUITE 1000 TRIDENT BLDG
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM NO. 184-0097
PROFESSIONAL DESIGN FIRM NO. 184-000897 CORPORATION
(217) 793-8894, (217) 793-5227 FILE NAME: c:\idot\schedulep2-10.dgn

COMPUTER FILE NO. SCHEDULEP2-10
PROJECT 03145
09/05/07-WCB

IDOTPL-50 1"=50' 8/07/00