DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	(115)RS-1	LIVINGSTON	279	35
STA.	155+00	TO STA.	161+00	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 66375

0 20 40
SCALE IN FEET

N

85'

STA. 9+06.56
MATCH EXISTING

HOT-MIX ASPHALT SURFACE
REMOVAL - BUTT JOINT
26.2 SQ. YD.

LOIS SANCKEN

EXISTING ROW

50' TAPER
BUTT JOINT

CHERRY ST.
(HMA)

EXISTING ROW

AGGREGATE PARKING LOT

O SAW AND TOOL INC.

LARRY B. & DEBORAH A. MEREDITH

TEMPORARY CONSTRUCTION EASEMENT

32 FOOT ADJUSTING 6" WATER MAIN

STORM SEWER REMOVAL
12" - 60 FOOT

STATION 155+00.00
BEGIN SECTION (115)RS-1

TELE. PED

CROP LINE

LANDSCAPING AREA

SIDEWALK REMOVAL
110 SQ. FT.

DONALD J.
DAGRAS

0 20 40
SCALE IN FEET

DRIVEWAY PAVEMENT
REMOVAL 29.9 SQ. YD.

75' TRANSITION & HMA
PAVEMENT REMOVAL - BUTT JOINT

PAVEMENT REMOVAL
9.9 SQ. YD.

12" CONC. SEWER

PAVEMENT REMOVAL
68.1 SQ. YD.

TBA

SIDEWALK

P.O.T. STA. 156+86.01
88°23'19"
91°36'41"
90°35'54"
89°24'06"

STA. 157+22.62, 18.98' LT.
EXIST. INLET
RIM = 682.23
FL = 679.63
TBR

℄ FAP RTE. 681
(IL RTE. 116)

P.O.T. STA. 160+00.00

STA. 161+00 MATCH LINE

HOT-MIX ASPHALT SURFACE
REMOVAL-BUTT JOINT
217.4 SQ. YD.

PAVEMENT REMOVAL
5.9 SQ. YD.

PAVEMENT REMOVAL
17.8 SQ. YD.

REL
(BY OTHERS)

REL
(BY OTHERS)

DRIVEWAY PAVEMENT
REMOVAL 47.2 SQ. YD.

SIDEWALK REMOVAL
593 SQ. FT.

DRIVEWAY PAVEMENT
REMOVAL 47.2 SQ. YD.

KIP & KREGG HARMS

CROP LINE

EXISTING R.O.W.

50' TAPER
BUTT JOINT

EXISTING R.O.W.

ROCK

STA. 156+87.85 ℄ FAP 681
STA. 10+00.00 ℄ CHERRY STREET

STA. 10+94.20
MATCH EXISTING

HOT-MIX ASPHALT SURFACE
REMOVAL - BUTT JOINT
26.5 SQ. YD.

ORVILLE & JEAN FLOYD

WELDON W. BRYDON

NORMAN T. WALKER

ALAN L. & BEVERLY D. METZ

BRICK

EARTH

AGG

LEGEND

SIDEWALK REMOVAL	
DRIVEWAY PAVEMENT REMOVAL	
HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	
PAVEMENT REMOVAL	
STORM SEWER PATCHES	
EXISTING PIPE CULVERT REMOVAL	
TREE REMOVAL	
TO BE RELOCATED	REL
TO BE REMOVED	TBR
TO BE ADJUSTED	TBA

REVISIONS	
NAME	DATE
IDOT	1-30-09

ILLINOIS DEPARTMENT OF TRANSPORTATION

REMOVAL AND ADJUSTMENT PLAN

FAP 681 (IL RTE. 116)
SECTION (115)RS-1
LIVINGSTON COUNTY
VILLAGE OF CULLOM

SCALE: VERT.
HORIZ.
DATE: 06/30/03

DRAWN BY: JAMESON
DESIGNED BY: BOTT
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
2200 WEST EDWARDS STREET
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM NO. 184-001279
PROFESSIONAL SERVICE INDUSTRY CORPORATION
(217) 793-3894, (217) 793-3277 FAX E-MAIL: coolbrookmail@cfonline.com

COMPUTER FILE NO.
REMOVAL116AP2-01

PROJECT: 03145
09/05/07-WCB