DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	(115)RS-1	LIVINGSTON	279	39
STA.	178+00	TO STA.	184+00	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 66375

1. STORM SEWER REMOVAL 12" = 5 FOOT
2. STORM SEWER REMOVAL 12" = 32 FOOT
3. STORM SEWER REMOVAL 18" = 32 FOOT
4. STORM SEWER TO BE FILLED = 47 FOOT

5. STA. 178+91.77, 41.51' RT.
EXIST. INLET (14" DIA.)
RIM = 677.63
FL (SW-15") = 675.33
FL (S-15") = 676.93
INV. = 673.61
TBR

6. STA. 179+35.37, 24.91' RT.
EXIST. INLET (24" DIA.)
RIM = 677.00
FL (NE-15") = 675.72
FL (SW-15") = 675.65
INV. = 672.82
TBR

7. STA. 179+53.81, 22.12' LT.
EXIST. INLET (24" DIA.)
RIM = 676.56
FL (NE-15") = 674.33
FL (W-10") = 674.66
INV. = 674.30
TBR

N

0 20 40
SCALE IN FEET

STA. 178+00 MATCHLINE

STA. 184+00 MATCHLINE

90 FOOT ADJUSTING 6" WATER MAIN

STA. 69+07.00 MATCH EXISTING

REMOVE EXISTING CULVERTS = 135 FOOT (6x4 RC BOX CULVERT)

STA. 179+20.46 ℄ FAP 681
STA. 70+00.00 ℄ OAK ST.

ROBERT A. OLSEN

P.C.C. DRIVE

PAVEMENT REMOVAL 26.6 SQ. YD.

OAK ST.

A-3 SURFACE

EXISTING ROW

50' TAPER

RONALD NETTLEINGHAM

RICHARD K. TURNER ETAL

RONALD & MARY A. PLATZ

KIM EHLERS

REL (BY OTHERS)

SIDEWALK REMOVAL 184 SQ. FT.

CURB REMOVAL 63'

SIDEWALK REMOVAL 98 SQ. FT.

DRIVEWAY PAVEMENT REMOVAL 45.9 SQ. YD.

SIDEWALK REMOVAL 232 SQ. FT.

DRIVEWAY PAVEMENT REMOVAL 48.3 SQ. YD.

PAVEMENT REMOVAL 99.7 SQ. YD.

CHRISTINA R. COSTAL

SIDEWALK REMOVAL 120 SQ. FT.

STA. 79+06.45 MATCH EXISTING

ELM STREET

(A-3 SURFACE)

REL

STA. 183+39.00 ℄ FAP 681
STA. 80+00.00 ℄ ELM ST.

PAVEMENT REMOVAL 101 SQ. YD.

DRIVEWAY PAVEMENT REMOVAL 27.9 SQ. YD.

NORTHERN ILLINOIS GAS SIGN

TBR

℄ FAP RTE. 681 (IL RTE. 116)

STA. 179+07.88 ℄ FAP 681
STA. 70+00.00 ℄ OAK ST.

STA. 183+17.76 ℄ FAP 681
STA. 80+00.00 ℄ ELM ST.

90°35'42" 89°24'18" 90°02'05" 89°57'55" 90°44'23" 89°15'37" 90°00'00" 90°00'00"

PAVEMENT REMOVAL 18.8 SQ. YD.

25 FOOT ADJUSTING WATER SERVICE LINES

TBR INLET

25 FOOT ADJUSTING WATER SERVICE LINES

25 FOOT ADJUSTING WATER SERVICE LINES

PAVEMENT REMOVAL 203.1 SQ. YD.

6" BARRIER CURB

GAS VAR.

6" BARRIER CURB

CONC. SIDEWALK

6" BARRIER CURB

STA. 180+00.00 35.32' RT.

CURB REMOVAL 24'

SIDEWALK REMOVAL 494 SQ. FT.

12" PVC. INLET

ISLANDS

DRIVEWAY PAVEMENT REMOVAL 84.1 SQ. YD.

SIDEWALK REMOVAL 261 SQ. FT.

STA. 179+82.00 45.00' RT.

DRIVEWAY PAVEMENT REMOVAL 114.1 SQ. YD.

P.C.C. PARKING LOT PAVEMENT

CURB REMOVAL 24 FOOT

SIDEWALK REMOVAL 98 SQ. FT.

SIDEWALK REMOVAL 113 SQ. FT.

PAVEMENT REMOVAL 88.7 SQ. YD.

SIDEWALK REMOVAL 152 SQ. FT.

REMOVE STUMP

CULLOM AMERICAN LEGION

CASEY'S GENERAL STORE

TERRY A. FEAZIL

JOHN R. WALTERS

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT 22.6 SQ. YD.

STA. 70+93.00 MATCH EXISTING

STA. 80+93.00 MATCH EXISTING

BM #2: STA. 183+42.15
NE CAP BOLT OF FIRE HYDRANT @ SE CORNER OF ELM ST./ ILL. RTE. 116
ELEV=684.98

LEGEND

SIDEWALK REMOVAL	
DRIVEWAY PAVEMENT REMOVAL	
HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	
PAVEMENT REMOVAL	
STORM SEWER PATCHES	
EXISTING PIPE CULVERT REMOVAL	
TREE REMOVAL	
TO BE RELOCATED	REL
TO BE REMOVED	TBR
TO BE ADJUSTED	TBA

REVISIONS	
NAME	DATE
FAV	12/08
IDOT	1-30-09

ILLINOIS DEPARTMENT OF TRANSPORTATION

REMOVAL AND ADJUSTMENT PLAN

FAP 681 (IL RTE. 116)
SECTION (115)RS-1
LIVINGSTON COUNTY
VILLAGE OF CULLOM

SCALE: VERT.
HORIZ.
DATE: 06/30/03

DRAWN BY: JAMESON
DESIGNED BY: BOTT
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
2121 SOUTH 6TH STREET
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM NO. 184-001179
PROFESSIONAL SERVICES FOR: FINAL ENGINEERING CORPORATION
(217) 753-0040, (217) 753-6227 (FAX), e-mail: gbsp@greenebradford.com

COMPUTER FILE NO.
REMOVAL116BP2-02
PROJECT: 03145
09/05/07-WCB