

MAINLINE											
STATION TO STATION	MIX CRS JTS & FLWYS	LEV BIND (HM) N50	BIT MAT (PR CT)	AGG (PR CT)	HMA SURF REM 1 1/2"	EXC & GRAD EXIST SHLD	HMA SHLD 6"	LEV BIND (MM) N50	HMA SURF CSE "C", N50	AGG WEDGE SHLD TY B	TEMP RAMP
	TON	TON	GAL	TON	SQ YD	UNIT	SQ YD	TON	TON	TON	SQ YD
GRUNDY											
23+18 - 23+48	0.02	0.04	11.4	0.2	73.0	0.6	15		7	2	12.2
23+48 - 64+38	3.00	5.00	1559.7	24.0	9998.0	81.8	2000	513	993	233	
64+38 - 277+65	17.06	28.44	8748.9	134.6	56872.0	426.5	10427	2878	5573	1215	
277+65 - 278+05	(SN 032-2004)		8.6	0.2	107.0				9		
278+05 - 378+25	8.04	13.40	4119.8	63.4	26720.0	200.4	4899	1355	2625	571	
378+25 - 379+25	(SN 032-2008)		35.5	0.9	444.0				37		
379+25 - 383+50	0.33	0.56	105.8	2.6	1133.0	8.5	208		110	24	
383+50 - 387+00	0.28	0.47	143.7	2.2	933.0	7.0	171	47	92	20	
LIVINGSTON											
387+00 - 392+07	0.41	0.68	208.0	3.2	1352.0	10.1	248	69	132	29	
392+07 - 392+97	0.07	0.12	36.9	0.6	120.0	1.8	44	4	24	6	13.3
TOTALS	29	49	14978	232	97752	737	18012	4866	9602	2100	26

PATCHING	
LOCATION	CLASS D PATCH 13 INCH SQ YD
BEGIN JOB TO GORMAN RD(4000E)	14 @ 8
GORMAN RD(4000E) TO STONEWALL RD(10000S)	16 @ 8
STONEWALL RD(10000S) TO SN 032-2004	9 @ 8
SN 032-2004 TO SCULLY RD(11000S)	4 @ 8
SCULLY RD(11000S) TO OLD MAZON RD(1000E)	5 @ 8
OLD MAZON RD(1000E) TO SN 032-2004	8 @ 8
TOTALS	448

SIDEROADS AND ENTRANCES							
STATION	TYPE	SIDE	BIT MATLS PR CT	AGG PR CT	INC HMA SURF	TEMP RAMP	HMA SURF REMOVAL 1 1/2"
			GALLON	TON	TON	SQ YD	SQ YD
MAHER RD	SR	LT	10	0.3	11	11.1	129
DIBBLE TRUCK	CE	RT	11		11		130
DIBBLE TRUCK	CE	RT	11		11		130
IDOT	CE	LT	4		4		45
IDOT	CE	LT	4		4		45
106+39 (4000E)	SR	LT	10	0.3	16	11.1	45
106+39 (4000E)	SR	RT	11	0.3	17	11.1	45
162+65	PE	LT	2		4		3
181+79	PE	LT	2		4		3
223+08 (10000S)	SR	LT	10	0.3	16	9.1	45
298+34 (11000S)	SR	LT	10	0.3	16	11.1	45
306+56	PE	RT	2		4		3
330+00 (1000E)	SR	LT	10	0.3	16	9.1	45
356+00 (DWIGHT RD)	SR	LT	10	0.2	15	11.1	45
TOTALS			107	1.8	148	74	758

PAVEMENT MARKING			
LOCATION	PAINT PAVT MK LINE 4"	PAINT PAVT MK LINE 6"	RAISED REFL PVT MARK
	WHITE	YELLOW	
STA. TO STA.	FOOT	FOOT	EACH
GRUNDY			
23+18 - 387+00			
CENTERLINE		9090	454
EDGELINES	72764		
LIVINGSTON			
387+00 - 392+97			
CENTERLINE		150	8
EDGELINES	1194		
TOTALS	73958	9240	462

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
os:\pwwork\pwwork\IDOT\DUNCANBD\dms84568\alshfts.dgn	DRAWN -	REVISED -	298			*	**	7	5	
PLOT SCALE = 50.000' / IN.	CHECKED -	REVISED -	* (7X-3,7R-2,6R-2)RS-1 & 92RS-2							
PLOT DATE = Jan 30, 2009 - 08:23:22 AM	DATE -	REVISED -	CONTRACT NO. 66494							
						ILLINOIS FED. AID PROJECT				

\*\* LIVINGSTON & GRUNDY

SCALE: SHEET NO. OF SHEETS STA. TO STA.