

SUMMARY OF QUANTITIES					100% FEDERAL	
CODE NO.	CONSTRUCTION CODE TYPE:		TOTAL QUANTITY	1000		
	ITEM	UNIT		PUTNAM COUNTY	LASALLE COUNTY	
20400800	FURNISHED EXCAVATION	CU YD	17	8	9	
25000200	SEEDING, CLASS 2	ACRE	0.11	0.05	0.06	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	5	5	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	5	5	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	5	5	
25100630	EROSION CONTROL BLANKET	SQ YD	572	260	312	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	21084	6551	14533	
40600300	AGGREGATE (PRIME COAT)	TON	402	125	277	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30	9	21	
40600525	LEVELING BINDER (HAND METHOD), N50	TON	50	15	35	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	4213	1288	2925	
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.3	0.7	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1387	495	892	
40600990	TEMPORARY RAMP	SQ YD	270	104	166	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	8426	2575	5851	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	265	114	151	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	103279	30964	72315	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1905	604	1301	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	229	0	229	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1	0.3	0.7	

SUMMARY OF QUANTITIES (CONTINUED)					100% FEDERAL	
CODE NO.	CONSTRUCTION CODE TYPE:		TOTAL QUANTITY	1000		
	ITEM	UNIT		PUTNAM COUNTY	LASALLE COUNTY	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	6	1	5	
67100100	MOBILIZATION	L SUM	1	0.3	0.7	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.3	0.7	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14250	3183	11067	
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	46.8	0	46.8	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	101639	28401	73238	
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	10607	2566	8041	
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	304	0	304	
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	136	0	136	
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	70	0	70	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1583	354	1229	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	552	133	419	
78200300	PRISMATIC CURB REFLECTOR	EACH	62	0	62	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	552	133	419	
X7800600	URETHANE PAVEMENT MARKING - LETTERS & SYMBOLS, SPECIAL	SQ FT	140.4	0	140.4	
X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	111977	28401	83576	
X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	13436	2566	10870	
X7800640	URETHANE PAVEMENT MARKING - LINE 8"	FOOT	1418	0	1418	
X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	304	0	304	
X7800680	URETHANE PAVEMENT MARKING - LINE 24"	FOOT	136	0	136	
Z0055300	RUMBLE STRIP	EACH	3	3	0	

▪ SPECIALTY ITEMS