

TEMPORARY PAVEMENT MARKING SCHEDULE										
LOCATION STA TO STA	LENGTH FOOT	TEMPORARY PVMT MARK- LINE 4"		TEMPORARY PVMT MARK- LINE 6"	TEMPORARY PVMT MARK- LINE 8"	TEMPORARY PVMT MARK- LINE 12"	TEMPORARY PVMT MARK- LINE 24"	TEMPORARY PVMT MARK- LET & SYMB	SHORT TERM PVMT MARK	WORK ZONE PVMT MARK REM
		WHITE FOOT	YELLOW FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	WHITE FOOT	WHITE SQ FT	FOOT	SQ FT
PUTNAM COUNTY										
3+17.3 TO 109+28.5	10611.2	21222		2566					3183	354
NO PASSING ZONE:										
9+22 TO 21+23 EBL			1201							
18+44 TO 25+56 WBL			712							
41+44 TO 51+80 EBL			1036							
51+80 TO 58+99 WBL			719							
68+18 TO 77+56 EBL			938							
78+22 TO 86+29 WBL			807							
92+91 TO 101+71 EBL			880							
100+43 TO 109+28.5 WBL			886							
PUTNAM SUBTOTAL		21222	7179	2566	0	0	0	0	3183	354
LASALLE COUNTY										
109+28.5 TO 140+02 BK	3073.5	6147		768					921	102
140+00 AH TO 154+98 BK	1498	2996		375					450	50
154+96 AH TO 328+81	17385	34770		4346					5217	580
328+81 TO 330+00	10119	20238		2530					3036	337
330+00 TO 373+08	4308	2354	1800	22	152	68	35	46.8	1305	145
373+08 TO 377+69	461	922	800		152	68	35		138	15
NO PASSING ZONES:										
144+69 TO 152+62 EBL			793							
153+22 TO 161+91 WBL			869							
291+70 TO 299+87 EBL			817							
302+36 TO 309+68 WBL			732							
LASALLE SUBTOTAL		67427	5811	8041	304	136	70	46.8	11067	1229
PROJECT TOTAL	47455.7	101639		10607	304	136	70	46.8	14250	1583

SEEDING SCHEDULE								
LOCATION		SIDE	SEEDING	FURN	EROSION	NIT	PHOS	POT
			CL 2	EXC	CONTROL	FERT	FERT	FERT
			ACRE	CU YD	BLANKET	NUT	NUT	NUT
					SQ YD	LB	LB	LB
PUTNAM								
PEORIA STREET	14+37	RT	0.01	1.5	52	0.9	0.9	0.9
CHICAGO STREET	18+96	RT	0.01	1.5	52	0.9	0.9	0.9
MOREL ROAD	20+44	LT	0.01	1.5	52	0.9	0.9	0.9
MERIDIAN ROAD	108+14	LT	0.01	1.5	52	0.9	0.9	0.9
1600E ROAD	108+14	RT	0.01	1.5	52	0.9	0.9	0.9
SUBTOTAL PUTNAM			0.05	7.5	260	4.5	4.5	4.5
LASALLE								
EAST 1ST ROAD	160+89	RT	0.01	1.5	52	0.9	0.9	0.9
EAST 1ST ROAD	160+89	LT	0.01	1.5	52	0.9	0.9	0.9
EAST 3rd ROAD	268+18	RT	0.01	1.5	52	0.9	0.9	0.9
EAST 3rd ROAD	268+18	LT	0.01	1.5	52	0.9	0.9	0.9
US 251	373+08.0	RT	0.01	1.5	52	0.9	0.9	0.9
US 251	373+08.0	LT	0.01	1.5	52	0.9	0.9	0.9
SUBTOTAL LASALLE			0.06	9	312	5.4	5.4	5.4
PROJECT TOTAL			0.11	16.5	572	9.9	9.9	9.9