

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: I000

URBAN
100% FEDERAL
TOTAL
QUANTITY

CODE NO.	ITEM	UNIT	QUANTITY
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2753
40600300	AGGREGATE (PRIME COAT)	TON	36
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	6
40600545	LEVELING BINDER (HAND METHOD), N90	TON	9
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	726
40600990	TEMPORARY RAMP	SQ YD	1143
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1449
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	17245
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1847
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4575
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13479
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1190
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	324
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	235
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	48
• 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 6"	FOOT	1190
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	69
• X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	13479
• X7800640	URETHANE PAVEMENT MARKING - LINE 8"	FOOT	324
• X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	235
• X7800680	URETHANE PAVEMENT MARKING - LINE 24"	FOOT	48

• SPECIALTY ITEM